

# EXPLORATORY BORING NO. 7

Date Drilled: 12/26/07

Client: Riverside Community Hospital

Equipment: CME 75 Track Rig

Driving Weight / Drop: 140 lbs./ 30 in.

Surface Elevation(ft): 825.0

Logged by: JMZ

Measured Depth to Water(ft): N.A.

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES		BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
				DRIVE	BULK				
		(SP) Sand, fine to coarse with gravel to 1", light brown		X		13 26 21			SPT
40				X		10 15 17		SPT	
45				X		14 50		SPT	
50				X		18 27 29		SPT	
		END OF BORING							
55		NO BEDROCK NO REFUSAL FILL TO 4.0' SLIGHT CAVING NO FREE GROUNDWATER							
60									
65									

BORING LOG - NO EQUIV & BLOW PER 6 IN 07881-3.GPJ CHJ.GDT 1/18/08



**C.H.J.**

PROPOSED HOSPITAL EXPANSION AND PARKING GARAGE Job No. 07881-3  
RIVERSIDE, CALIFORNIA

Enclosure  
**B-7b**

# EXPLORATORY BORING NO. 8

Date Drilled: 12/21/07

Client: Riverside Community Hospital

Equipment: Limited Access Mole Rig

Driving Weight / Drop: 140 lbs./ 30 in.

Surface Elevation(ft): 810.0

Logged by: TAD

Measured Depth to Water(ft): N.A.

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES		BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
				DRIVE	BULK				
5	[Stippled Pattern]	(SM) Silty Sand, fine with clay, dark brown	Fill		[Cross-hatched]		14.2		
				[X]		22 28 30	13.4	122	Ring
10	[Stippled Pattern]	(SM) Silty sand, fine with clay, dark brown.	Native		[X]	7 8 8	4.8	99	Ring
					[X]	3 3 4	6.0	138	Ring
15	[Stippled Pattern]	(ML) Sandy Silt, fine with clay, dark brown			[X]	5 6 7	N.R.	N.R.	Ring
					[X]	7 8 8	20.8	104	Ring
25	[Stippled Pattern]	(SP) Sand, fine to coarse with gravel to 3", light brown			[X]	10 15 30	1.6	114	Ring
					[X]	40 50	4.6	113	Ring
		END OF BORING							
		NO BEDROCK, REFUSAL AT 31.0' FILL TO 7.0', SLIGHT CAVING NO FREE GROUNDWATER							

BORING LOG - NO EQUIV & BLOW PER 6 IN 07881-3.GPJ CHJ.GDT 1/18/08



**C.H.J.**

PROPOSED HOSPITAL EXPANSION AND PARKING GARAGE Job No. 07881-3  
RIVERSIDE, CALIFORNIA

Enclosure  
**B-8**

# EXPLORATORY BORING NO. 9

Date Drilled: 12/21/07

Client: Riverside Community Hospital

Equipment: Limited Access Mole Rig

Driving Weight / Drop: 140 lbs./ 30 in.

Surface Elevation(ft): 811.0

Logged by: TAD

Measured Depth to Water(ft): N.A.

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES		BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
				DRIVE	BULK				
		(SM) Silty Sand, fine, medium brown	Fill		XXXX		8.5		
5		(SM) Silty Sand, fine with clay, dark brown		X		14 14 15	8.7	127	Ring, Pass #200
10		(ML) Sandy Silt, fine with clay, light brown	Native		XXXX		10.7		
				X		4 4 5	4.9	98	Ring
15				X		2 3 5	7.6	101	Ring, DS
20				X		7 10 11	8.2	115	Ring
25		(SP) Sand, fine with medium to coarse, light brown		X		8 10 25	1.9	113	Ring
30		END OF BORING		X		9 11 29	5.3	107	Ring
		NO BEDROCK REFUSAL AT 29.5' FILL TO 9.0' SLIGHT CAVING NO FREE GROUNDWATER							


BORING LOG - NO EQUIV & BLOW PER 6 IN 07881-3.GPJ CHJ/GDT 1/18/08



**C.H.J.**

PROPOSED HOSPITAL EXPANSION AND PARKING GARAGE Job No. 07881-3  
RIVERSIDE, CALIFORNIA

Enclosure  
**B-9**



**CHJ BORING LOG OF 12/20/07**

SILTY SAND (SM) WITH GRAVEL FILL  
 DRY UNIT WEIGHT = 120 pcf  
 BLOW COUNTS = 14

SILTY SAND (SM)  
 DRY UNIT WEIGHT = 101-120 pcf  
 BLOW COUNT = 4-7

SAND (SP) WITH GRAVEL  
 DRY UNIT RATE = 104-117 pcf  
 BLOW COUNTS = 12-50

SAND (SP) WITH GRAVEL & COBBLES  
 DRY UNIT RATE = 111-134 pcf  
 BLOW COUNTS = >50

REFUSAL @ 70 feet - NO BEDROCK

**VELOCITY CORRELATIONS WITH STRATIGRAPHY**

DEPTH RANGE (feet)	COMPRESSONAL VELOCITY (ft/sec)	SHEAR VELOCITY (ft/sec)	STRATIGRAPHY
0 - 12	1020 +/- 7%	280 +/-15%	SILTY SAND (SM) WITH GRAVEL FILL
12 - 31	1600 +/-12%	460 +/-10%	SILTY SAND (SM)
31 - 42	3500 +/-10%	700 +/-13%	SAND (SP) WITH GRAVEL
42 - 66	5750 +/-10%	1940 +/-12%	SAND (SP) WITH GRAVEL AND COBBLES

**EXPLANATION**  
 MEASUREMENT DEPTHS RELATIVE TO GROUND SURFACE AT CASING, NOT CASING TOP. SEISMIC ENERGY SOURCE OFFSET IS 8.0 feet. ADJUSTED TIME AXIS CALCULATED AS TRAVEL TIME MULTIPLIED BY THE RATIO OF THE MEASUREMENT DEPTH DIVIDED BY SLANT DISTANCE TRAVELED BY THE SEISMIC WAVES SO THE DATA APPEARS AS VERTICALLY INCIDENT.

- COMPRESSIONAL WAVE DATA
- HORIZONTALLY POLARIZED SHEAR WAVE DATA
- INTERPRETED SEISMIC VELOCITY WITH ESTIMATED UNCERTAINTY

**FIGURE 2**  
**BORING B1**  
 DOWNHOLE SEISMIC VELOCITY DATA AND INTERPRETED VELOCITY MODEL WITH STRATIGRAPHIC CORRELATIONS  
 PROPOSED BED TOWER & PARKING GARAGE  
 RIVERSIDE COMMUNITY HOSPITAL  
 TERRA PHYSICS




# C.H.J. Inc

Location Riverside Community Hospital  
 Job Number 07881-3  
 Hole Number CPT-01  
 Water Table Depth \_\_\_\_\_

Operator ML/JH  
 Cone Number DSG1047  
 Date and Time 12/20/2007 8:22:44 AM  
 0.00 ft

Filename SDF(502).cpt  
 GPS \_\_\_\_\_  
 Maximum Depth 53.15 ft  
 Elevation 838 ft






# C.H.J. Inc

Location Riverside Community Hospital  
 Job Number 07881-3  
 Hole Number CPT-02  
 Water Table Depth \_\_\_\_\_

Operator ML/JH  
 Cone Number DSG1047  
 Date and Time 12/20/2007 9:16:17 AM  
 0.00 ft

Filename SDF(503).cpt  
 GPS \_\_\_\_\_  
 Maximum Depth 54.30 ft  
 Elevation 839 ft






# C.H.J. Inc

Location Riverside Community Hospital  
 Job Number 07881-3  
 Hole Number CPT-03  
 Water Table Depth \_\_\_\_\_

Operator ML/JH  
 Cone Number DSG1047  
 Date and Time 12/20/2007 10:07:56 AM  
 \_\_\_\_\_

Filename SDF(504).cpt  
 GPS \_\_\_\_\_  
 Maximum Depth 55.12 ft  
 Elevation 837 ft






# C.H.J. Inc

**Location** Riverside Community Hospital  
**Job Number** 07881-3  
**Hole Number** CPT-04  
**Water Table Depth** \_\_\_\_\_

**Operator** ML/JH  
**Cone Number** DSG1047  
**Date and Time** 12/20/2007 11:43:15 AM  
**0.00 ft**

**Filename** SDF(505).cpt  
**GPS** \_\_\_\_\_  
**Maximum Depth** 16.73 ft  
**Elevation** 797 ft








# C.H.J. Inc

**Location** Riverside Community Hospital  
**Job Number** 07881-3  
**Hole Number** CPT-05  
**Water Table Depth** \_\_\_\_\_

**Operator** ML/JH  
**Cone Number** DSG1047  
**Date and Time** 12/20/2007 12:28:45 PM  
**Water Table Depth** 0.00 ft

**Filename** SDF(506).cpt  
**GPS** \_\_\_\_\_  
**Maximum Depth** 24.28 ft  
**Elevation** 798 ft






# C.H.J. Inc

**Location** Riverside Community Hospital  
**Job Number** 07881-3  
**Hole Number** CPT-06  
**Water Table Depth** \_\_\_\_\_

**Operator** ML/JH  
**Cone Number** DSG1047  
**Date and Time** 12/20/2007 1:04:18 PM  
**0.00 ft**

**Filename** SDF(507).cpt  
**GPS** \_\_\_\_\_  
**Maximum Depth** 4.43 ft  
**Elevation** 797 ft

## CPT DATA



- |                            |                               |                              |                                  |
|----------------------------|-------------------------------|------------------------------|----------------------------------|
| 1 - sensitive fine grained | 4 - silty clay to clay        | 7 - silty sand to sandy silt | 10 - gravelly sand to sand       |
| 2 - organic material       | 5 - clayey silt to silty clay | 8 - sand to silty sand       | 11 - very stiff fine grained (*) |
| 3 - clay                   | 6 - sandy silt to clayey silt | 9 - sand                     | 12 - sand to clayey sand (*)     |

Depth Increment

\*Soil behavior type and SPT based on data from UBC-1983

# EXPLORATORY BORING NO. 1

Date Drilled: 10/20/12

Client: HCA Management Services, LP

Equipment: CME 55

Driving Weight / Drop: 130 lbs./30"

Surface Elevation(ft): 793.5

Logged by: VJR

Measured Depth to Water(ft): N/A

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES		UNCORRECTED BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
				DRIVE	BULK				
		3.5" of Asphalt Concrete	Fill						
		5" of Aggregate Base							
		(SM) Silty Sand, fine to medium with coarse, with clay, brown		X	X	3 1 4	11.5		Cor., RV,SA,SE SPT
5		(SM) Silty Sand, fine to medium, brown	Native	X	X	1 1 2	10.1		Cor., DS, Exp., Hydro., MDC,SA SPT, P#200
10		(SM) Silty Sand, fine to medium with gravel to 2", brown		X	X	2 2 3	3.1		SPT, P#200
15		(SM) Silty Gravelly Sand, fine to medium with coarse and gravel to 2", brown		X	X	10 30 50/3"			SPT, P#200
20				X	X	37 50/5"			SPT, P#200
25				X	X	22 38 39			SPT, P#200
30				X	X	50 50/4"			SPT, P#200

BORING LOG - NO EQUIV & BLOW PER 6 IN. 12735-3.GPJ CHJ.GDT 11/21/12



MEDICAL OFFICE BUILDING  
RIVERSIDE COMMUNITY HOSPITAL

Job No. Enclosure  
12735-3 B-1a

# EXPLORATORY BORING NO. 1

Date Drilled: 10/20/12

Client: HCA Management Services, LP

Equipment: CME 55

Driving Weight / Drop: 130 lbs./30"

Surface Elevation(ft): 793.5

Logged by: VJR

Measured Depth to Water(ft): N/A

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES		UNCORRECTED BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
				DRIVE	BULK				
		(SM) Silty Sand, fine to coarse, with clay and gravel to 2", light brown		X		48 50/4"			SPT. P#200
40		END OF BORING							
		NO BEDROCK REFUSAL AT 37.0' FILL TO 3.0', SLIGHT CAVING NO GROUNDWATER							
45									
50									
55									
60									
65									

BORING LOG - NO EQUIV & BLOW PER 6 IN. 12735-3.GPJ CHJ.GDT 11/21/12



MEDICAL OFFICE BUILDING  
RIVERSIDE COMMUNITY HOSPITAL

Job No. Enclosure  
12735-3 B-1b

# EXPLORATORY BORING NO. 2

Date Drilled: 10/24/12

Client: HCA Management Services, LP

Equipment: CME75

Driving Weight / Drop: 130 lbs./30"

Surface Elevation(ft): 792.5

Logged by: JMc

Measured Depth to Water(ft): 37.5

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES		UNCORRECTED BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
				DRIVE	BULK				
		6" of Asphalt Concrete	Fill						
		5" of Aggregate Base					10.5		Cor., RV, SA, SE
5		(SM) Silty Sand, fine to medium, few clay and gravel to 1/2", brown	Native				8.2		Cor., DS, Exp., Hydro., MDC, SA
		(SM) Silty Sand, fine with medium, brown							SPT, P#200
10		(SP-SM) Sand with silt, fine to medium with coarse, brown				3 4 4	4.9		SPT, P#200
		(SP-SM) Sand, fine to coarse with silt, brown				2 3 4			SPT, P#200
15		(SM) Silty Gravelly Sand, fine to medium with coarse, gravel to 1", brown				20 30 27			SPT, P#200
20		(SM) Silty Gravelly Sand, fine to medium with coarse, gravel to 1", brown				32 27 27			SPT, P#200
25		(SM) Silty Gravelly Sand, fine to medium with coarse, gravel to 1", brown				39 50/5"			SPT, P#200
30		(SM) Silty Gravelly Sand, fine to medium with coarse, gravel to 1", brown				50/5"			SPT, P#200

BORING LOG - NO EQUIV & BLOW PER 6 IN - 12735-3.GPJ CHJ/GDT 11/21/12



MEDICAL OFFICE BUILDING  
RIVERSIDE COMMUNITY HOSPITAL

Job No. Enclosure  
12735-3 B-2a

# EXPLORATORY BORING NO. 2

Date Drilled: 10/24/12

Client: HCA Management Services, LP

Equipment: CME75

Driving Weight / Drop: 130 lbs./30"

Surface Elevation(ft): 792.5

Logged by: JMc

Measured Depth to Water(ft): 37.5

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES		UNCORRECTED BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
				DRIVE	BULK				
40	[Stippled Pattern]	(SM) Silty Gravelly Sand, fine to medium with coarse, gravel to 1", brown	▼	[X]		50/3"			SPT, P#200
45	[Stippled Pattern]		[X]			50			SPT, P#200
50	[Stippled Pattern]		[X]			41 50/4"			SPT, P#200
55	[Stippled Pattern]		[X]			50/4"			SPT, P#200
60	[Stippled Pattern]	END OF BORING							
65	[Stippled Pattern]	NO BEDROCK NO REFUSAL FILL TO 3.5' NO CAVING GROUNDWATER AT 37.5'							

BORING LOG - NO EQUIV & BLOW PER 6 IN 12735-3 GPJ CHJ GDT 11/21/12



MEDICAL OFFICE BUILDING  
RIVERSIDE COMMUNITY HOSPITAL

Job No. Enclosure  
12735-3 B-2b

# BORING 1

DATE DRILLED: January 11, 2013  
 EQUIPMENT USED: Rotary Wash  
 HOLE DIAMETER (in.): 5"  
 ELEVATION: 796\*\*

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. LATITUDE AND LONGITUDE OF BORING LOCATION SHOWN ON LOGS ARE APPROXIMATE; REFER TO PLOT PLAN FOR MORE ACCURATE LOCATION INFORMATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER. INTERFACES BETWEEN STRATA ARE APPROXIMATE. TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

ELEVATION (ft)	DEPTH (ft)	"N" VALUE STD. PEN. TEST	MOISTURE (% of dry wt.)	DRY DENSITY (pcf)	BLOW COUNT* (blows/ft)	SAMPLE LOC.	
795							4" thick Asphalt Concrete over 3" thick Base Course
	5		11.3	93	7		SANDY SILT - medium stiff, moist, yellowish brown and olive yellow, some fine to coarse sand, some mica
790			24.6	92	12		
	10	7					Becomes olive brown to olive yellow, (68% passing No. 200 sieve)
785			4.3	104	17		
	15	17					WELL-GRADED SAND with SILT - medium dense, moist, olive yellow to yellowish brown, fine to coarse grained, some fine gravel (up to 1/2 inch in size), layers of Poorly Graded Sand
780			7.7	125	93/11"		
	20						Becomes very dense, some fine gravel (up to 3/4 inch in size)
775		78					
	25		7.9	120	53/6"		
770							Cobbles (up to 8 inches in size)
	30	64					Becomes fine to medium grained
765			15.5	120	50/5"		WELL-GRADED SAND with SILT and GRAVEL - very dense, wet, olive yellow, fine to coarse grained, fine gravel (up to 3/4 inch in size)
	35	55/6"					Increasing coarse sand and fine gravel
760			17.3	113	66/5"		Cobble (up to 10 inches in size)
	40						Granitic rock and cobbles (up to 6 inches in size)

(CONTINUED ON FOLLOWING FIGURE)

Field Tech: AR  
 Prepared By: LH  
 Checked By: LT 10/5/2012

**Proposed Bed Tower Expansion  
 Riverside Community Hospital  
 Riverside, California**



**LOG OF BORING**

Project: 4953-13-0001

Figure: A-1.1a

B:\2501L\_CRANDALL\DECIMAL\_ELE\LA70131\_GEOTECH\GINTW\LIBRARY\_AMEC\JUNE2012\GLB PA4953\_GEOTECH\2013-PROJ\130001\_RIVERSIDE\_COMMUNITY\_HOSP\3.2\_ALL\_FIELD\_NOTES\130001\_GPJ\_2/28/13

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. LATITUDE AND LONGITUDE OF BORING LOCATION SHOWN ON LOGS ARE APPROXIMATE; REFER TO PLOT PLAN FOR MORE ACCURATE LOCATION INFORMATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER. INTERFACES BETWEEN STRATA ARE APPROXIMATE. TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## BORING 1 (Continued)

DATE DRILLED: January 11, 2013  
 EQUIPMENT USED: Rotary Wash  
 HOLE DIAMETER (in.): 5"  
 ELEVATION: 796\*\*

ELEVATION (ft)	DEPTH (ft)	"N" VALUE STD.PEN.TEST	MOISTURE (% of dry wt.)	DRY DENSITY (pcf)	BLOW COUNT* (blows/ft)	SAMPLE LOC.
755	52/6"					SM
						SW
750	45		--	--	73/6"	
745	50	50/5"				
740	55					
735	60					
730	65					
725	70					
720	75					
	80					

SILTY SAND - very dense, wet, light brown, fine to medium grained, granitic rock fragments

WELL-GRADED SAND with GRAVEL - very dense, wet, light brown, fine to coarse grained, some cobbles (up to 5 inches in size)  
 Cobbles (up to 5 inches in size)

Sample not recovered, 4-inch cobble

Layers of Poorly Graded Sand  
 END OF BORING AT 50 FEET

NOTES:

Drilling mud used during drilling process. Mud removed after completion of drilling to a depth of 33 feet. Water level measured at a depth of 31.5 feet after removal of drilling mud and a depth of 31.4 feet 15 minutes later. Boring backfilled with a cement bentonite grout

\*Number of blows to drive the Crandall sampler 12 inches using a 140 pound automatic hammer falling 30 inches.

\*\* Elevation based on topographic survey included on Enclosure A-2.1 of the report dated 1/22/08 by C.H.J. Incorporated.

Field Tech: AR  
 Prepared By: LH  
 Checked By: LT 10/5/2012

Proposed Bed Tower Expansion  
 Riverside Community Hospital  
 Riverside, California



## LOG OF BORING

Project: 4953-13-0001

Figure: A-1.1b



# BORING 2

DATE DRILLED: January 11, 2013  
 EQUIPMENT USED: Rotary Wash  
 HOLE DIAMETER (in.): 5"  
 ELEVATION: 794\*\*

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. LATITUDE AND LONGITUDE OF BORING LOCATION SHOWN ON LOGS ARE APPROXIMATE; REFER TO PLOT PLAN FOR MORE ACCURATE LOCATION INFORMATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER. INTERFACES BETWEEN STRATA ARE APPROXIMATE. TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

ELEVATION (ft)	DEPTH (ft)	"N" VALUE STD.PEN.TEST	MOISTURE (% of dry wt.)	DRY DENSITY (pcf)	BLOW COUNT* (blows/ft)	SAMPLE LOC.	DESCRIPTION
790	5		19.0	104	11	SM	4" thick Asphalt Concrete over 6" thick Base Course SILTY SAND - loose, moist, yellowish brown, fine to coarse grained, trace fine gravel (up to 1/4 inch in size)
785	10		14.7	111	21	SW	WELL-GRADED SAND - medium dense, moist, olive yellow to light brownish gray, fine to coarse grained, some gravel
780	15	49				SP-SM	POORLY GRADED SAND - dense, moist, olive yellow to yellowish brown, fine to coarse grained, some fine gravel (up to 1/2 inch in size) POORLY GRADED SAND with SILT - dense to very dense, moist, olive to brown, fine to medium, trace fine gravel (up to 1/2 inch in size)
775	20	78	--	--	30/0"		Some cobbles, sample not recovered
770	25	50/6"			75/6"	SW	Sample not recovered, 4-inch cobble WELL-GRADED SAND with GRAVEL - very dense, moist, olive yellow to light brownish gray, fine to coarse grained, granitic rock fragments, fine to coarse gravel (up to 2 inches in size) Becomes olive, some silt
765	30		10.2	115	85		Some silty sand interbeds
760	35	85					
755	40	56/6"	11.0	116	53/6"		

(CONTINUED ON FOLLOWING FIGURE)

Field Tech: AR  
 Prepared By: LH  
 Checked By: LT 10/5/2012

**Proposed Bed Tower Expansion  
 Riverside Community Hospital  
 Riverside, California**



## LOG OF BORING

Project: 4953-13-0001

Figure: A-1.2a

# BORING 2 (Continued)

DATE DRILLED: January 11, 2013  
 EQUIPMENT USED: Rotary Wash  
 HOLE DIAMETER (in.): 5"  
 ELEVATION: 794\*\*

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. LATITUDE AND LONGITUDE OF BORING LOCATION SHOWN ON LOGS ARE APPROXIMATE; REFER TO PLOT PLAN FOR MORE ACCURATE LOCATION INFORMATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER. INTERFACES BETWEEN STRATA ARE APPROXIMATE. TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

ELEVATION (ft)	DEPTH (ft)	"N" VALUE STD.PEN.TEST	MOISTURE (% of dry wt.)	DRY DENSITY (pcf)	BLOW COUNT* (blows/ft)	SAMPLE LOC.
750	45		22.4	106	63/6"	SW
745	50	97/9"				
740	55					
735	60					
730	65					
725	70					
720	75					
715	80					

Cobbles (up to 8 inches in size)

Less silt, more gravel, granitic rock fragments

END OF BORING AT 49½ FEET

NOTES:

Caving encountered below a depth of 29 feet after removal of drilling mud. Unable to measure water level. Boring backfilled with a cement bentonite grout.

Field Tech: AR  
 Prepared By: LH  
 Checked By: LT 10/5/2012

**Proposed Bed Tower Expansion  
 Riverside Community Hospital  
 Riverside, California**



## LOG OF BORING

Project: 4953-13-0001

Figure: A-1.2b

**APPENDIX B**  
**LABORATORY TESTING**

---

## APPENDIX B

### LABORATORY TESTING

Laboratory testing was conducted in a manner consistent with the level of care and skill ordinarily exercised by members of the profession currently practicing under similar conditions and in the same locality. No warranty, express or implied, is made as to the correctness or serviceability of the test results, or the conclusions derived from these tests. Where a specific laboratory test method has been referenced, such as ASTM or Caltrans, the reference only applies to the specified laboratory test method, which has been used only as a guidance document for the general performance of the test and not as a "Test Standard". A brief test description follows.

**Classification:** Soils were visually classified according to the Unified Soil Classification System as established by the American Society of Civil Engineers per ASTM D2487. The soil classifications are shown on the boring logs in Appendix A.

**Particle Size Analysis:** Particle size analyses were performed in accordance with ASTM D422 and were used to supplement the visual soil classifications. The test results and associated soil classifications are summarized in Figures B-1.1 through B-1.12.

**Atterberg Limits:** ASTM D4318 was used to determine the liquid and plastic limits, and plasticity index of a selected clayey soil sample. The results are shown in selected Figures B-1.1 to B-1.12.

**Expansion Index:** The expansion potentials of selected soil samples were estimated in general accordance with the laboratory procedures outlined in ASTM D4829. The test results are summarized in Figure B-2, along with common criteria for evaluating the expansion potential.

**pH and Resistivity:** To assess the potential for reactivity with buried metals, selected soil samples were tested for pH and minimum saturated resistivity using Caltrans test method 643. The corrosivity test results are summarized in Figure B-3.

**Sulfate Content:** To assess the potential for reactivity with concrete, selected soil samples were tested for water soluble sulfate. The sulfate was extracted from the soil under vacuum using a 10:1 (water to dry soil) dilution ratio, and then tested for water soluble sulfate using ASTM D516. These test results are also shown in Figure B-3, along with criteria for evaluating soluble sulfate content.

**Chloride Content:** Soil samples were also tested for water soluble chloride. The chloride was extracted from the soil under vacuum using the 10:1 (water to dry soil) dilution ratio described above. The extracted solutions were then tested for water soluble chloride using a calibrated ion specific electronic probe. These test results are also shown in Figure B-3.

## APPENDIX B


### LABORATORY TESTING (Continued)

**Consolidation:** The one-dimensional consolidation properties of selected samples were evaluated in general accordance with ASTM D2435. The samples were inundated with water under a nominal seating load, allowed to swell, and then subjected to controlled stress increments while restrained laterally and drained axially. The test results are presented in Figures B-4.1 and B-4.2.

**Direct Shear:** The shear strengths of selected materials were assessed using direct shear testing conducted on relatively undisturbed soil samples in general accordance with ASTM D3080. The shear test results are shown in Figures B-5.1 to B-5.4. The tests are summarized in Figure B-5.5.

**R-Value:** R-Value tests were performed on selected samples of the subgrade soils collected from the site in general accordance with CTM 301. The test results are shown in Figure B-6.1 and B-6.2.






COARSE	FINE	COARSE	MEDIUM	FINE	SILT AND CLAY
GRAVEL		SAND			

SAMPLE	
EXPLORATION ID:	B-1
SAMPLE DEPTH:	0' - 5'

<b>UNIFIED SOIL CLASSIFICATION:</b>	SM
<b>DESCRIPTION:</b>	SILTY SAND

ATTERBERG LIMITS	
LIQUID LIMIT:	---
PLASTIC LIMIT:	---
PLASTICITY INDEX:	---

	<b>GROUP DELTA</b>	<b>SOIL CLASSIFICATION</b>	Document No. 24-0011
			Project No. SD809




COARSE	FINE	COARSE	MEDIUM	FINE	SILT AND CLAY
GRAVEL		SAND			

SAMPLE	
EXPLORATION ID:	B-1
SAMPLE DEPTH:	20' - 21½'

<b>UNIFIED SOIL CLASSIFICATION:</b>	CL
<b>DESCRIPTION:</b>	LEAN CLAY

ATTERBERG LIMITS	
LIQUID LIMIT:	37
PLASTIC LIMIT:	19
PLASTICITY INDEX:	18

 <b>GROUP DELTA</b>	<b>SOIL CLASSIFICATION</b>	Document No. 24-0011	
			Project No. SD809
			<b>FIGURE B-1.2</b>



COARSE	FINE	COARSE	MEDIUM	FINE	SILT AND CLAY
GRAVEL		SAND			


SAMPLE	
EXPLORATION ID:	B-2
SAMPLE DEPTH:	10' - 11½'

<b>UNIFIED SOIL CLASSIFICATION:</b>	SM
<b>DESCRIPTION:</b>	SILTY SAND

ATTERBERG LIMITS	
LIQUID LIMIT:	---
PLASTIC LIMIT:	---
PLASTICITY INDEX:	---

 <b>GROUP DELTA</b>	<b>SOIL CLASSIFICATION</b>	Document No. 24-0011	
			Project No. SD809
			<b>FIGURE B-1.3</b>






COARSE	FINE	COARSE	MEDIUM	FINE	SILT AND CLAY
GRAVEL		SAND			

SAMPLE	
EXPLORATION ID:	B-2
SAMPLE DEPTH:	20' - 21½'

<b>UNIFIED SOIL CLASSIFICATION:</b>	CL
<b>DESCRIPTION:</b>	LEAN CLAY

ATTERBERG LIMITS	
LIQUID LIMIT:	46
PLASTIC LIMIT:	22
PLASTICITY INDEX:	24

 <b>GROUP DELTA</b>	<b>SOIL CLASSIFICATION</b>	Document No. 24-0011	
			Project No. SD809
			<b>FIGURE B-1.4</b>




COARSE	FINE	COARSE	MEDIUM	FINE	SILT AND CLAY
GRAVEL		SAND			

SAMPLE	
EXPLORATION ID:	B-3
SAMPLE DEPTH:	1/2' - 5'

<b>UNIFIED SOIL CLASSIFICATION:</b>	SM
<b>DESCRIPTION:</b>	SILTY SAND

ATTERBERG LIMITS	
LIQUID LIMIT:	---
PLASTIC LIMIT:	---
PLASTICITY INDEX:	---

 <b>GROUP DELTA</b>	<b>SOIL CLASSIFICATION</b>	Document No. 24-0011	
			Project No. SD809
			<b>FIGURE B-1.5</b>




COARSE	FINE	COARSE	MEDIUM	FINE	SILT AND CLAY
GRAVEL		SAND			

SAMPLE	
EXPLORATION ID:	B-4
SAMPLE DEPTH:	5' - 6½'

<b>UNIFIED SOIL CLASSIFICATION:</b>	SM
<b>DESCRIPTION:</b>	SILTY SAND

ATTERBERG LIMITS	
LIQUID LIMIT:	---
PLASTIC LIMIT:	---
PLASTICITY INDEX:	---

 <b>GROUP DELTA</b>	<b>SOIL CLASSIFICATION</b>	Document No. 24-0011	
			Project No. SD809
			<b>FIGURE B-1.6</b>




COARSE	FINE	COARSE	MEDIUM	FINE	SILT AND CLAY
GRAVEL		SAND			

SAMPLE	
EXPLORATION ID:	B-5
SAMPLE DEPTH:	5' - 6½'

<b>UNIFIED SOIL CLASSIFICATION:</b>	ML
<b>DESCRIPTION:</b>	SANDY SILT

ATTERBERG LIMITS	
LIQUID LIMIT:	---
PLASTIC LIMIT:	---
PLASTICITY INDEX:	---

 <b>GROUP DELTA</b>	<b>SOIL CLASSIFICATION</b>	Document No. 24-0011	
			Project No. SD809
			<b>FIGURE B-1.7</b>




COARSE	FINE	COARSE	MEDIUM	FINE	SILT AND CLAY
GRAVEL		SAND			

SAMPLE	
EXPLORATION ID:	B-6
SAMPLE DEPTH:	1/2' - 5'

<b>UNIFIED SOIL CLASSIFICATION:</b>	SC
<b>DESCRIPTION:</b>	CLAYEY SAND

ATTERBERG LIMITS	
LIQUID LIMIT:	---
PLASTIC LIMIT:	---
PLASTICITY INDEX:	---

 <b>GROUP DELTA</b>	<b>SOIL CLASSIFICATION</b>	Document No. 24-0011	
			Project No. SD809
			<b>FIGURE B-1.8</b>




COARSE	FINE	COARSE	MEDIUM	FINE	SILT AND CLAY
GRAVEL		SAND			

SAMPLE	
EXPLORATION ID:	B-7
SAMPLE DEPTH:	10' - 11½'

<b>UNIFIED SOIL CLASSIFICATION:</b>	ML
<b>DESCRIPTION:</b>	SANDY SILT

ATTERBERG LIMITS	
LIQUID LIMIT:	---
PLASTIC LIMIT:	---
PLASTICITY INDEX:	---

 <b>GROUP DELTA</b>	<b>SOIL CLASSIFICATION</b>	Document No. 24-0011	
			Project No. SD809
			<b>FIGURE B-1.9</b>




COARSE	FINE	COARSE	MEDIUM	FINE	SILT AND CLAY
GRAVEL		SAND			

SAMPLE	
EXPLORATION ID:	B-8
SAMPLE DEPTH:	0' - 5'

<b>UNIFIED SOIL CLASSIFICATION:</b>	SM
<b>DESCRIPTION:</b>	SILTY SAND

ATTERBERG LIMITS	
LIQUID LIMIT:	---
PLASTIC LIMIT:	---
PLASTICITY INDEX:	---

	<b>GROUP DELTA</b>	<b>SOIL CLASSIFICATION</b>	Document No. 24-0011
			Project No. SD809
			<b>FIGURE B-1.10</b>



COARSE	FINE	COARSE	MEDIUM	FINE	SILT AND CLAY
GRAVEL		SAND			


SAMPLE	
EXPLORATION ID:	B-9
SAMPLE DEPTH:	10' - 11½'

<b>UNIFIED SOIL CLASSIFICATION:</b>	ML
<b>DESCRIPTION:</b>	SANDY SILT

ATTERBERG LIMITS	
LIQUID LIMIT:	---
PLASTIC LIMIT:	---
PLASTICITY INDEX:	---

 <b>GROUP DELTA</b>	<b>SOIL CLASSIFICATION</b>	Document No. 24-0011	
			Project No. SD809
			<b>FIGURE B-1.11</b>





COARSE	FINE	COARSE	MEDIUM	FINE	SILT AND CLAY
GRAVEL		SAND			

SAMPLE	
EXPLORATION ID:	B-10
SAMPLE DEPTH:	1' - 5'

<b>UNIFIED SOIL CLASSIFICATION:</b>	ML
<b>DESCRIPTION:</b>	SANDY SILT

ATTERBERG LIMITS	
LIQUID LIMIT:	---
PLASTIC LIMIT:	---
PLASTICITY INDEX:	---

 <b>GROUP DELTA</b>	<b>SOIL CLASSIFICATION</b>	Document No. 24-0011	
			Project No. SD809
			<b>FIGURE B-1.12</b>

**EXPANSION TEST RESULTS**  
(ASTM D4829)

SAMPLE ID	DESCRIPTION	EXPANSION INDEX
B-3 @ ½' – 5'	<b>Fill:</b> Yellowish brown silty sand (SM).	0
B-6 @ ½' – 5'	<b>Fill:</b> Dark yellowish brown silty sand (SM).	1
B-8 @ 0' – 5'	<b>Fill:</b> Brown silty sand (SM).	0
B-10 @ 1' – 5'	<b>Fill:</b> Yellowish brown sandy silt (ML).	1

EXPANSION INDEX	POTENTIAL EXPANSION
0 to 20	Very low
21 to 50	Low
51 to 90	Medium
91 to 130	High
Above 130	Very High



**LABORATORY TEST RESULTS**

Document No. 24-0011

Project No. SD809

**FIGURE B-2**

**CORROSIVITY TEST RESULTS**  
(ASTM D516)

SAMPLE ID	pH	RESISTIVITY [OHM-CM]	SULFATE CONTENT [%]	CHLORIDE CONTENT [%]
B-3 @ ½' – 5'	7.7	4,230	< 0.01	< 0.01
B-6 @ ½' – 5'	8.4	3,220	< 0.01	< 0.01
B-8 @ 0' – 5'	8.2	3,610	< 0.01	< 0.01
B-10 @ 1' – 5'	7.7	2,460	< 0.01	< 0.01

SULFATE CONTENT [%]	SULFATE EXPOSURE	CEMENT TYPE
0.00 to 0.10	Negligible	-
0.10 to 0.20	Moderate	II, IP(MS), IS(MS)
0.20 to 2.00	Severe	V
Above 2.00	Very Severe	V plus pozzolan

SOIL RESISTIVITY [OHM-CM]	GENERAL DEGREE OF CORROSIVITY TO FERROUS METALS
0 to 1,000	Very Corrosive
1,000 to 2,000	Corrosive
2,000 to 5,000	Moderately Corrosive
5,000 to 10,000	Mildly Corrosive
Above 10,000	Slightly Corrosive

CHLORIDE (Cl) CONTENT [%]	GENERAL DEGREE OF CORROSIVITY TO METALS
0.00 to 0.03	Negligible
0.03 to 0.15	Corrosive
Above 0.15	Severely Corrosive




**LABORATORY TEST RESULTS**

Document No. 24-0011

Project No. SD809

**FIGURE B-3**



**Sample:**

B-1 @ 20' - 21½'  
*(Water added at seating load)*

**Description:**

Yellow brown lean clay (CL)  
 (Estimated field curve in RED)

**Results**

Po:	2507	[psf]
Pc:	6600	[psf]
OCR:	2.6	
Cc:	0.214	
Cs:	0.044	

**Initial Final**


Height:	1.0000	0.9434	[in]
Dry Density:	102.4	108.5	[pcf]
Void Ratio (e):	0.676	0.574	
Water Content:	22.4	21.0	[%]
Saturation:	91	100	[%]

Note: To find the traditional compression (Cc) and swell (Cs) indices, the values in strain domain were multiplied by 1.68 (or 1+e)



**GROUP DELTA CONSOLIDATION RESULTS**

Document No. 24-0011  
 Project No. SD809  
**FIGURE B-4.1**



**Sample:**

B-2 @ 20' - 21½'  
*(Water added at seating load)*

**Description:**

Dark yellow brown lean clay (CL)  
 (Estimated field curve in RED)

**Results**

Po:	2587	[psf]
Pc:	7800	[psf]
OCR:	3.0	
Cc:	0.195	
Cs:	0.053	

**Initial Final**



Height:	1.0000	0.9831	[in]
Dry Density:	105.6	107.4	[pcf]
Void Ratio (e):	0.710	0.648	
Water Content:	22.6	22.9	[%]
Saturation:	90	100	[%]

Note: To find the traditional compression (Cc) and swell (Cs) indices, the values in strain domain were multiplied by 1.71 (or 1+e)



**GROUP DELTA CONSOLIDATION RESULTS**

Document No. 24-0011  
 Project No. SD809  
**FIGURE B-4.2**



**SAMPLE:** B-2 @ 10' - 11½'

**Young Alluvium (Qya):**  
Dark yellowish brown silty sand (SM)

**PEAK**

$\phi'$	38 °
$C'$	300 PSF

**ULTIMATE**

$\phi'$	38 °
$C'$	200 PSF

**STRAIN RATE:** 0.0030 IN/MIN  
(Sample was consolidated and drained)

**IN-SITU**

$\gamma_d$	108.6 PCF
$w_c$	3.2 %



**AS-TESTED**

$\gamma_d$	108.6 PCF
$w_c$	15.4 %



**GROUP DELTA DIRECT SHEAR TEST RESULTS**

Document No. 24-0011  
Project No. SD809  
**FIGURE B-5.1**



**SAMPLE:** B-4 @ 5' - 6½'

**Young Alluvium (Qya):**  
Yellowish brown silty sand (SM)

**PEAK**

$\phi'$	39 °
$C'$	200 PSF

**ULTIMATE**

$\phi'$	39 °
$C'$	100 PSF

**STRAIN RATE:** 0.0030 IN/MIN  
(Sample was consolidated and drained)

**IN-SITU**

$\gamma_d$	112.3 PCF
$w_c$	9.4 %



**AS-TESTED**

$\gamma_d$	112.3 PCF
$w_c$	15.7 %



**GROUP DELTA DIRECT SHEAR TEST RESULTS**

Document No. 24-0011  
Project No. SD809  
**FIGURE B-5.2**



**SAMPLE:** B-10 @ 10' - 11½'

**Artificial Fill (Qya):**  
Yellowish brown silty sand (SM)

**PEAK**

$\phi'$	37 °
$c'$	200 PSF

**ULTIMATE**

$\phi'$	37 °
$c'$	100 PSF

**STRAIN RATE:** 0.0030 IN/MIN  
(Sample was consolidated and drained)

**IN-SITU**

$\gamma_d$	98.5 PCF
$w_c$	5.8 %

**AS-TESTED**



$\gamma_d$	98.5 PCF
$w_c$	26.3 %



**GROUP DELTA DIRECT SHEAR TEST RESULTS**

Document No. 24-0011  
Project No. SD809  
**FIGURE B-5.3**





**SAMPLE:** B-10 @ 20' - 21½'

**Artificial Fill (Qya):**  
Brownish yellow sandy silt (ML)

**STRAIN RATE:** 0.0002 IN/MIN  
(Sample was consolidated and drained)

**PEAK**

$\phi'$	30 °
$c'$	400 PSF

**IN-SITU**

$\gamma_d$	98.5 PCF
$w_c$	11.2 %

**ULTIMATE**

$\phi'$	30 °
$c'$	300 PSF


**AS-TESTED**

$\gamma_d$	98.5 PCF
$w_c$	26.3 %



**GROUP DELTA DIRECT SHEAR TEST RESULTS**

Document No. 24-0011  
Project No. SD809  
**FIGURE B-5.4**



**DESCRIPTION**

A summary of direct shear tests conducted on samples of the sandy fill and alluvium collected from the Garage and Tower sites at the Riverside Community Hospital.

**PEAK ESTIMATE**

$\phi'$	37 °
$C'$	200 PSF

**ULTIMATE ESTIMATE**

$\phi'$	36 °
$C'$	150 PSF



SAMPLE NO.: B-6

SAMPLE DATE: 4/3/24

SAMPLE LOCATION: 1/2' - 5'

TEST DATE: 4/12/24

SAMPLE DESCRIPTION: Dark yellowish brown clayey sand (SC)

### LABORATORY TEST DATA

TEST SPECIMEN	1	2	3	4	5	
A COMPACTOR PRESSURE	350	350	350			[PSI]
B INITIAL MOISTURE	2.5	2.5	2.5			[%]
C BATCH SOIL WEIGHT	1200	1200	1200			[G]
D WATER ADDED	75	85	102			[ML]
E WATER ADDED (D*(100+B)/C)	6.4	7.3	8.7			[%]
F COMPACTION MOISTURE (B+E)	8.9	9.8	11.2			[%]
G MOLD WEIGHT	2009.7	2016.1	2009.1			[G]
H TOTAL BRIQUETTE WEIGHT	3083.5	3170.7	3160.9			[G]
I NET BRIQUETTE WEIGHT (H-G)	1073.8	1154.6	1151.8			[G]
J BRIQUETTE HEIGHT	2.38	2.43	2.55			[IN]
K DRY DENSITY (30.3*I/((100+F)*J))	125.5	131.2	123.1			[PCF]
L EXUDATION LOAD	7490	5459	3109			[LB]
M EXUDATION PRESSURE (L/12.54)	597	435	248			[PSI]
N STABILOMETER AT 1000 LBS	14	20	39			[PSI]
O STABILOMETER AT 2000 LBS	24	33	73			[PSI]
P DISPLACEMENT FOR 100 PSI	4.33	5.04	6.93			[Turns]
Q R VALUE BY STABILOMETER	77	66	30			
R CORRECTED R-VALUE (See Fig. 14)	75	64	30			
S EXPANSION DIAL READING	0.0016	0.0007	0.0002			[IN]
T EXPANSION PRESSURE (S*43,300)	69	30	9			[PSF]
U COVER BY STABILOMETER	0.23	0.34	0.65			[FT]
V COVER BY EXPANSION	0.53	0.23	0.07			[FT]

TRAFFIC INDEX:	5.0
GRAVEL FACTOR:	1.72
UNIT WEIGHT OF COVER [PCF]:	130
R-VALUE BY EXUDATION:	40
R-VALUE BY EXPANSION:	68
R-VALUE AT EQUILIBRIUM:	40

\*Note: Gravel factor estimated from pavement section using CTM 301, Section C, Part b.

REV. 2, DATED 1/31/15





### R-VALUE TEST RESULTS CT301

Document No. 24-0011  
Project No. SD809  
FIGURE B-6.1a

Sample: B-6 @ 1/2' - 5'

R-Value at Equilibrium: 40



SAMPLE NO.: B-8

SAMPLE DATE: 4/1/24

SAMPLE LOCATION: 0' - 5'

TEST DATE: 4/12/24

SAMPLE DESCRIPTION: Dark yellowish brown silty sand (SM)

### LABORATORY TEST DATA

TEST SPECIMEN	1	2	3	4	5	
A COMPACTOR PRESSURE	290	250	210			[PSI]
B INITIAL MOISTURE	2.2	2.2	2.2			[%]
C BATCH SOIL WEIGHT	1200	1200	1200			[G]
D WATER ADDED	90	100	105			[ML]
E WATER ADDED (D*(100+B)/C)	7.7	8.5	8.9			[%]
F COMPACTION MOISTURE (B+E)	9.9	10.7	11.1			[%]
G MOLD WEIGHT	2004.8	2007.6	2074.3			[G]
H TOTAL BRIQUETTE WEIGHT	3155.6	3197.7	3202.9			[G]
I NET BRIQUETTE WEIGHT (H-G)	1150.8	1190.1	1128.6			[G]
J BRIQUETTE HEIGHT	2.57	2.62	2.53			[IN]
K DRY DENSITY (30.3*I/((100+F)*J))	123.5	124.3	121.6			[PCF]
L EXUDATION LOAD	4172	3211	2450			[LB]
M EXUDATION PRESSURE (L/12.54)	333	256	195			[PSI]
N STABILOMETER AT 1000 LBS	39	45	46			[PSI]
O STABILOMETER AT 2000 LBS	76	96	97			[PSI]
P DISPLACEMENT FOR 100 PSI	6.55	6.74	7.18			[Turns]
Q R VALUE BY STABILOMETER	30	20	18			
R CORRECTED R-VALUE (See Fig. 14)	31	22	18			
S EXPANSION DIAL READING	0.0000	0.0000	0.0000			[IN]
T EXPANSION PRESSURE (S*43,300)	0	0	0			[PSF]
U COVER BY STABILOMETER	0.70	0.79	0.83			[FT]
V COVER BY EXPANSION	0.00	0.00	0.00			[FT]

TRAFFIC INDEX:	5.0
GRAVEL FACTOR:	1.58
UNIT WEIGHT OF COVER [PCF]:	130
R-VALUE BY EXUDATION:	27
R-VALUE BY EXPANSION:	100
R-VALUE AT EQUILIBRIUM:	27

\*Note: Gravel factor estimated from pavement section using CTM 301, Section C, Part b.

REV. 2, DATED 1/31/15





### R-VALUE TEST RESULTS CT301

Document No. 24-0011  
Project No. SD809  
FIGURE B-6.2a

Sample: B-8 @ 0' - 5'

R-Value at Equilibrium: 27



**APPENDIX C**  
**LIQUEFACTION ANALYSIS**

---

## APPENDIX C

### LIQUEFACTION ANALYSES

Liquefaction analyses were performed using the data gathered from the CPT soundings. The results are shown in Figures C-1 to C-5. The analyses were based on the procedures originally developed by Seed and Idriss and were conducted in general accordance with the recommended procedures for liquefaction analyses described in Section C4.4 of ASCE 61-14 (ASCE, 2014). The tip resistance ( $q_t$ ) was normalized for overburden pressure and corrected for fines content (Youd et al., 2001). The fines correction was based on the Soil Behavior Type Index  $I_c$  (Robertson, 2010).

For each CPT sounding, the uncorrected Cone Resistance, Normalized Cone Resistance, the Soil Behavior Type (SBT), Factor of Safety against liquefaction, and estimated vertical settlement are plotted versus depth. A high groundwater elevation corresponding to a depth of 25-feet below grade was assumed for the analyses based on available historic data from the site vicinity as well as the groundwater levels we encountered during our recent subsurface explorations. The seismic demand used for the liquefaction analyses was equal to the Maximum Considered Earthquake Geometric Mean acceleration adjusted for site effects ( $PGA_M$ ) for the Garage and Tower sites of 0.615g, based on the requirements of Section 11.8.3 of ASCE 7-16 for a Seismic Design Category D.


The vertical settlement plots for each CPT sounding show the estimated range of dynamic settlement resulting from a seismic demand equal to the  $PGA_M$  acceleration. At depths where the seismically induced shear stress exceeds the stress required to cause liquefaction, the Factor of Safety is less than 1.0, and seismic settlement may occur. Fine-grained soils with an  $I_c$  value greater than 2.6 are considered too clayey to liquefy, and granular soils with a normalized tip resistance greater than 160 are considered too dense to liquefy. Only soils that are both loose enough and sandy enough to liquefy contribute to the post-liquefaction settlement. Dry sand settlement above groundwater accounted for most of the estimated seismic settlement (Pradel, 1998). We assumed that a 10-foot-deep over-excavation below grade would be conducted for new building areas.

Each of the CPT analyses were conducted using three different assumptions. In the first figure for each CPT sounding (Case A), a spreadsheet was used to estimate seismic settlement with no data averaging. These analyses were then compared to results from a commercially available program CLiq V3.3.1.14, with the CPT data averaged across 3 depth increments (Case B), and with a thin layer correction applied (Case C). The results of these three parametric liquefaction analyses are tabulated below, along with the average settlement from the three different methods.

Exploration No.	A) Settlement (Raw CPT Data)	B) Settlement (Data Averaging)	C) Settlement (Thin Layer)	Average Settlement	Figure No.
CPT-1	0.8 Inches	0.6 Inches	0.5 Inches	<b>0.6 Inches</b>	C-1
CPT-2	1.3 Inches	1.0 Inches	1.0 Inches	<b>1.1 Inches</b>	C-2
CPT-3	0.0 Inches	0.0 Inches	0.0 Inches	<b>0.0 Inches</b>	C-3
CPT-4	1.9 Inches	2.7 Inches	2.7 Inches	<b>2.4 Inches</b>	C-4
CPT-5	0.5 Inches	0.3 Inches	0.3 Inches	<b>0.4 Inches</b>	C-5









**GROUP DELTA**

**DYNAMIC SETTLEMENT (CPT-1)**  
(Seismic Demand ~ 0.615g)




Document No. 24-0011  
Project No. SD809  
**FIGURE C-1a**



Analysis method:	NCEER (1998)	G.W.T. (in-situ):	30.00 ft	Use fill:	No	Clay like behavior	
Fines correction method:	NCEER (1998)	G.W.T. (earthq.):	25.00 ft	Fill height:	N/A	applied:	Sands only
Points to test:	Based on Ic value	Average results interval:	3	Fill weight:	N/A	Limit depth applied:	No
Earthquake magnitude $M_w$ :	7.00	Ic cut-off value:	2.60	Trans. detect. applied:	No	Limit depth:	N/A
Peak ground acceleration:	0.61	Unit weight calculation:	Based on SBT	$K_0$ applied:	Yes	MSF method:	Method based




Analysis method:	NCEER (1998)	G.W.T. (in-situ):	30.00 ft	Use fill:	No	Clay like behavior	
Fines correction method:	NCEER (1998)	G.W.T. (earthq.):	25.00 ft	Fill height:	N/A	applied:	Sands only
Points to test:	Based on Ic value	Average results interval:	3	Fill weight:	N/A	Limit depth applied:	No
Earthquake magnitude $M_w$ :	7.00	Ic cut-off value:	2.60	Trans. detect. applied:	Yes	Limit depth:	N/A
Peak ground acceleration:	0.61	Unit weight calculation:	Based on SBT	$K_0$ applied:	Yes	MSF method:	Method based




**GROUP DELTA**

**DYNAMIC SETTLEMENT (CPT-2)**  
(Seismic Demand ~ 0.615g)


Document No. 24-0011  
Project No. SD809  
**FIGURE C-2a**



Analysis method:	NCEER (1998)	G.W.T. (in-situ):	30.00 ft	Use fill:	No	Clay like behavior	
Fines correction method:	NCEER (1998)	G.W.T. (earthq.):	25.00 ft	Fill height:	N/A	applied:	Sands only
Points to test:	Based on Ic value	Average results interval:	3	Fill weight:	N/A	Limit depth applied:	No
Earthquake magnitude $M_w$ :	7.00	Ic cut-off value:	2.60	Trans. detect. applied:	No	Limit depth:	N/A
Peak ground acceleration:	0.61	Unit weight calculation:	Based on SBT	$K_0$ applied:	Yes	MSF method:	Method based




Analysis method:	NCEER (1998)	G.W.T. (in-situ):	30.00 ft	Use fill:	No	Clay like behavior	
Fines correction method:	NCEER (1998)	G.W.T. (earthq.):	25.00 ft	Fill height:	N/A	applied:	Sands only
Points to test:	Based on Ic value	Average results interval:	3	Fill weight:	N/A	Limit depth applied:	No
Earthquake magnitude $M_w$ :	7.00	Ic cut-off value:	2.60	Trans. detect. applied:	Yes	Limit depth:	N/A
Peak ground acceleration:	0.61	Unit weight calculation:	Based on SBT	$K_0$ applied:	Yes	MSF method:	Method based



**GROUP DELTA**


**DYNAMIC SETTLEMENT (CPT-3)**  
(Seismic Demand ~ 0.615g)

Document No. 24-0011  
Project No. SD809  
**FIGURE C-3a**




Analysis method:	NCEER (1998)	G.W.T. (in-situ):	30.00 ft	Use fill:	No	Clay like behavior	
Fines correction method:	NCEER (1998)	G.W.T. (earthq.):	25.00 ft	Fill height:	N/A	applied:	Sands only
Points to test:	Based on Ic value	Average results interval:	3	Fill weight:	N/A	Limit depth applied:	No
Earthquake magnitude $M_w$ :	7.00	Ic cut-off value:	2.60	Trans. detect. applied:	No	Limit depth:	N/A
Peak ground acceleration:	0.61	Unit weight calculation:	Based on SBT	$K_0$ applied:	Yes	MSF method:	Method based






Analysis method:	NCEER (1998)	G.W.T. (in-situ):	30.00 ft	Use fill:	No	Clay like behavior	
Fines correction method:	NCEER (1998)	G.W.T. (earthq.):	25.00 ft	Fill height:	N/A	applied:	Sands only
Points to test:	Based on Ic value	Average results interval:	3	Fill weight:	N/A	Limit depth applied:	No
Earthquake magnitude $M_w$ :	7.00	Ic cut-off value:	2.60	Trans. detect. applied:	Yes	Limit depth:	N/A
Peak ground acceleration:	0.61	Unit weight calculation:	Based on SBT	$K_0$ applied:	Yes	MSF method:	Method based




**GROUP DELTA**

**DYNAMIC SETTLEMENT (CPT-4)**  
(Seismic Demand ~ 0.564g)




Document No. 24-0011  
Project No. SD809  
**FIGURE C-4a**



Analysis method:	NCEER (1998)	G.W.T. (in-situ):	30.00 ft	Use fill:	No	Clay like behavior	
Fines correction method:	NCEER (1998)	G.W.T. (earthq.):	25.00 ft	Fill height:	N/A	applied:	Sands only
Points to test:	Based on Ic value	Average results interval:	3	Fill weight:	N/A	Limit depth applied:	No
Earthquake magnitude $M_w$ :	7.00	Ic cut-off value:	2.60	Trans. detect. applied:	No	Limit depth:	N/A
Peak ground acceleration:	0.61	Unit weight calculation:	Based on SBT	$K_0$ applied:	Yes	MSF method:	Method based




Analysis method:	NCEER (1998)	G.W.T. (in-situ):	30.00 ft	Use fill:	No	Clay like behavior	
Fines correction method:	NCEER (1998)	G.W.T. (earthq.):	25.00 ft	Fill height:	N/A	applied:	Sands only
Points to test:	Based on Ic value	Average results interval:	3	Fill weight:	N/A	Limit depth applied:	No
Earthquake magnitude $M_w$ :	7.00	Ic cut-off value:	2.60	Trans. detect. applied:	Yes	Limit depth:	N/A
Peak ground acceleration:	0.61	Unit weight calculation:	Based on SBT	$K_0$ applied:	Yes	MSF method:	Method based




**GROUP DELTA**

**DYNAMIC SETTLEMENT (CPT-5)**  
(Seismic Demand ~ 0.615g)

Document No. 24-0011  
Project No. SD809  
**FIGURE C-5a**



Analysis method:	NCEER (1998)	G.W.T. (in-situ):	30.00 ft	Use fill:	No	Clay like behavior	
Fines correction method:	NCEER (1998)	G.W.T. (earthq.):	25.00 ft	Fill height:	N/A	applied:	Sands only
Points to test:	Based on Ic value	Average results interval:	3	Fill weight:	N/A	Limit depth applied:	No
Earthquake magnitude $M_w$ :	7.00	Ic cut-off value:	2.60	Trans. detect. applied:	No	Limit depth:	N/A
Peak ground acceleration:	0.56	Unit weight calculation:	Based on SBT	$K_0$ applied:	Yes	MSF method:	Method based



Analysis method:	NCEER (1998)	G.W.T. (in-situ):	30.00 ft	Use fill:	No	Clay like behavior	
Fines correction method:	NCEER (1998)	G.W.T. (earthq.):	25.00 ft	Fill height:	N/A	applied:	Sands only
Points to test:	Based on Ic value	Average results interval:	3	Fill weight:	N/A	Limit depth applied:	No
Earthquake magnitude $M_w$ :	7.00	Ic cut-off value:	2.60	Trans. detect. applied:	Yes	Limit depth:	N/A
Peak ground acceleration:	0.56	Unit weight calculation:	Based on SBT	$K_0$ applied:	Yes	MSF method:	Method based

***APPENDIX D***  
***INFILTRATION ASSESSMENT***

---



## APPENDIX D


### INFILTRATION ASSESSMENT

We understand that various detention basins, swales or pervious pavements will be incorporated into the development to help promote on-site infiltration. To aid in BMP design, the vertical infiltration rates were estimated at the six test locations provided in the RFP. The standard borehole percolation test method was used. The test configuration is depicted schematically below. The borehole percolation test method requires filling the borehole repeatedly to maintain a relatively constant water head throughout the test duration, while measuring the volume of water the percolates into the ground at specific time intervals. The approximate infiltration test locations are shown on the Exploration Plan, Figure 3A. The test results are presented in detail in the attached Figures D-1.1a through D-6.2b.

Per the County of Riverside BMP Design Manual, the borehole percolation test may be used for both planning level screening and BMP design purposes. Per the standards of practice, the percolation tests should be conducted at approximately the same depth and the same material as the base of the proposed storm water BMP. The Storm Water Manual also requires that two infiltration tests be conducted within 50-feet of each proposed BMP. We conducted two infiltration tests at each of the 6 BMP locations shown on the overall site Exploration Plan, Figure 3A.

The field infiltration tests were conducted in general accordance with the County of Riverside requirements. The borehole infiltration test wells were drilled to depths ranging from 3 to 8 feet below the ground surface. Prior to testing, each well was presoaked with water and allowed to drain. Water was then infiltrated into the soil with flow measurements taken at selected time intervals. Each infiltration test was continued until a relatively constant infiltration rate was attained for 60 minutes.

The field testing indicated preliminary factored infiltration rates that ranged widely from 0.02 to 1.32 inches per hour as shown in Figures D-1.1a through D-6.2b. A Factor of Safety of 2.0 is recommended for BMP design. Note that a factored infiltration rate above 0.50 inches per hour is commonly considered the minimum rate for effective "Full Infiltration" measures. An infiltration rate less than 0.05 inches per hour is commonly considered a "No Infiltration" condition.



# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/2/2024</u>	Borehole Radius (*r): <u>2 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/3/2024</u>	Casing Diameter: <u>2 in.</u>
Test Hole Number: <u>I-1A</u>	Tested By: <u>CRJ/DMG</u>	Depth of Hole: <u>5.3 ft</u>
Drilling Method: <u>Hand Auger</u>	Temperature: <u>75 F</u>	Gravel Base Thickness: <u>3 in.</u>

## DATA SHEET

Reading Number	Time Interval (min.)	Cumulative Time (min.)	Initial Depth to Water (ft.)	Final Depth to Water (ft.)	Avg. Height of Water above Gravel Base (in.)		Measured Drop in Water Level (in.)	Corrected Drop in Water Level <sup>1</sup> (in.)	Corrected Percolation Rate <sup>1</sup> (in./hour)	Unfactored Infiltration Rate* (in./hour)
					H <sub>avg</sub>	H <sub>int</sub>				
	Δt	T	[from ground surface]				ΔH	ΔH <sub>c</sub>	ΔH <sub>c</sub> /Δt	I <sub>t</sub>
25	2.0	80	3.53	3.73	19.4	10.1*r	2.4	1.4	42.9	1.85
26	2.0	82	3.73	3.92	17.1	8.7*r	2.3	1.4	40.8	1.98
27	2.0	84	3.92	4.08	15.0	7.4*r	1.9	1.1	34.3	1.89
28	2.0	86	4.08	4.23	13.1	6.3*r	1.8	1.1	32.2	2.01
29	2.0	88	4.23	4.33	11.6	5.3*r	1.2	0.7	21.5	1.50
30	2.0	90	4.33	4.44	10.4	4.6*r	1.3	0.8	23.6	1.83
31	2.0	92	4.44	4.54	9.1	3.8*r	1.2	0.7	21.5	1.88
32	2.0	94	2.75	3.09	28.0	15.4*r	4.1	2.4	72.9	2.21
33	2.0	96	3.09	3.35	24.4	13.1*r	3.1	1.9	55.8	1.93
34	2.0	98	3.35	3.57	21.5	11.3*r	2.6	1.6	47.2	1.85
35	2.0	100	3.57	3.76	19.0	9.8*r	2.3	1.4	40.8	1.79
36	2.0	102	3.76	3.93	16.9	8.5*r	2.0	1.2	36.5	1.80
37	2.0	104	3.93	4.07	15.0	7.3*r	1.7	1.0	30.0	1.66
38	2.0	106	4.07	4.18	13.5	6.4*r	1.3	0.8	23.6	1.44
39	2.0	108	4.18	4.31	12.1	5.6*r	1.6	0.9	27.9	1.89
40	2.0	110	4.31	4.42	10.6	4.7*r	1.3	0.8	23.6	1.80
41	2.0	112	4.42	4.51	9.4	4*r	1.1	0.6	19.3	1.64
42	2.0	114	2.85	3.15	27.0	14.7*r	3.6	2.1	64.4	2.02
43	2.0	116	3.15	3.38	23.8	12.7*r	2.8	1.6	49.3	1.75
44	2.0	118	3.38	3.59	21.2	11.1*r	2.5	1.5	45.1	1.79
45	2.0	120	3.59	3.73	19.1	9.7*r	1.7	1.0	30.0	1.32
46	2.0	122	3.73	3.89	17.3	8.7*r	1.9	1.1	34.3	1.65
47	2.0	124	3.89	4.01	15.6	7.6*r	1.4	0.9	25.7	1.37
48	2.0	126	4.01	4.14	14.1	6.8*r	1.6	0.9	27.9	1.63
49	2.0	128	4.14	4.24	12.7	5.9*r	1.2	0.7	21.5	1.38
50	2.0	130	4.24	4.34	11.5	5.2*r	1.2	0.7	21.5	1.51
51	2.0	132	4.34	4.44	10.3	4.5*r	1.2	0.7	21.5	1.68
52	2.0	134	4.44	4.52	9.2	3.8*r	1.0	0.6	17.2	1.48
53	3.0	137	2.81	3.17	27.1	15*r	4.3	2.6	51.5	1.61
54	2.0	139	3.17	3.34	23.9	12.5*r	2.0	1.2	36.5	1.29
55	2.0	141	3.34	3.50	22.0	11.4*r	1.9	1.1	34.3	1.32
56	2.0	143	3.50	3.65	20.1	10.3*r	1.8	1.1	32.2	1.34
57	2.0	145	3.65	3.80	18.3	9.3*r	1.8	1.1	32.2	1.47
58	2.0	147	3.80	3.90	16.8	8.2*r	1.2	0.7	21.5	1.06
59	2.0	149	3.90	4.02	15.5	7.5*r	1.4	0.9	25.7	1.38
60	2.0	151	4.02	4.14	14.0	6.7*r	1.4	0.9	25.7	1.51

1: Porosity of gravel assumed to be 0.4 to correct drop in water.  
 \*Porchet method used to convert percolation rate to infiltration rate.


**Stabilized, Unfactored Infiltration Rate\*:** 1.57 inch/hour

<b>HCA Design and Construction</b> Riverside Community Hospital Riverside, California	<b>BOREHOLE PERCOLATION TEST I-1A</b> <b>INFILTRATION RATE</b>	PROJECT NUMBER <b>SD809</b>	FIGURE NUMBER <b>D-1.1a</b>
---	---	--------------------------------	--------------------------------

# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/2/2024</u>	Borehole Radius (*r): <u>2 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/3/2024</u>	Casing Diameter: <u>2 in.</u>
Test Hole Number: <u>I-1A</u>	Tested By: <u>CRJ/DMG</u>	Depth of Hole: <u>5.3 ft</u>
Drilling Method: <u>Hand Auger</u>	Temperature <sup>3</sup> : <u>75 F</u>	Test Depth: <u>3½ to 4½ ft</u>

## UNFACTORED INFILTRATION RATES\* DURING TEST



**Preliminary Factored Infiltration Rate<sup>1</sup>: 0.64 in/hr**

**Feasibility Screening Factor of Safety, F.S.<sup>2</sup>: 2.0**

**Temperature Correction Factor<sup>2,3</sup>: 0.82**

Factored Infiltration Rate <sup>2</sup>	Design Condition <sup>2</sup>
Below 0.05	No Infiltration
0.05 to 0.50	Partial Infiltration
Above 0.50	Full Infiltration

\*Porchet method used to convert percolation rate to infiltration rate.  
 1: Rate Factored by Factor of Safety and Temperature Correction Factor.  
 2: Reference: Riverside Design Handbook for Low Impact Development BMP (2011).  
 3: Factor based on as-tested water temperature of 75 F and rainfall temperature of 60 F.

<b>HCA Design and Construction                  Riverside Community Hospital                  Riverside, California</b>	<b>BOREHOLE PERCOLATION TEST I-1A                  INFILTRATION RATE</b>	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="font-size: small;">PROJECT NUMBER</td> <td style="font-size: small;">FIGURE NUMBER</td> </tr> <tr> <td style="text-align: center;"><b>SD809</b></td> <td style="text-align: center;"><b>D-1.1b</b></td> </tr> </table>	PROJECT NUMBER	FIGURE NUMBER	<b>SD809</b>	<b>D-1.1b</b>
PROJECT NUMBER	FIGURE NUMBER					
<b>SD809</b>	<b>D-1.1b</b>					

# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/2/2024</u>	Borehole Radius (*r): <u>2 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/3/2024</u>	Casing Diameter: <u>2 in.</u>
Test Hole Number: <u>I-1B</u>	Tested By: <u>DMG</u>	Depth of Hole: <u>5.2 ft</u>
Drilling Method: <u>Hand Auger</u>	Temperature: <u>77 F</u>	Gravel Base Thickness: <u>3 in.</u>

## DATA SHEET

Reading Number	Time Interval (min.)	Cumulative Time (min.)	Initial Depth to Water (ft.)	Final Depth to Water (ft.)	Avg. Height of Water above Gravel Base (in.)		Measured Drop in Water Level (in.)	Corrected Drop in Water Level <sup>1</sup> (in.)	Corrected Percolation Rate <sup>1</sup> (in./hour)	Unfactored Infiltration Rate* (in./hour)
					H <sub>avg</sub>	H <sub>int</sub>				
	Δt	T	[from ground surface]				ΔH	ΔH <sub>c</sub>	ΔH <sub>c</sub> /Δt	I <sub>t</sub>
25	2.0	70	4.25	4.40	10.1	4.6*r	1.8	1.1	32.2	2.56
26	2.0	72	4.40	4.55	8.3	3.6*r	1.8	1.1	32.2	3.06
27	2.0	74	2.96	3.45	23.6	13.4*r	5.9	3.5	105.1	3.76
28	2.0	76	3.45	3.76	18.8	10.1*r	3.7	2.2	66.5	2.96
29	2.0	78	3.76	4.02	15.4	8*r	3.1	1.9	55.8	3.01
30	2.0	80	4.02	4.31	12.1	6.2*r	3.5	2.1	62.2	4.21
31	2.0	82	4.25	4.38	10.3	4.6*r	1.6	0.9	27.9	2.19
32	2.0	84	2.76	3.28	25.8	14.8*r	6.2	3.7	111.6	3.66
33	2.0	86	3.28	3.61	20.7	11.2*r	4.0	2.4	70.8	2.87
34	2.0	88	3.61	3.83	17.4	9*r	2.6	1.6	47.2	2.26
35	2.0	90	3.83	4.07	14.6	7.5*r	2.9	1.7	51.5	2.90
36	2.0	92	4.07	4.24	12.2	5.8*r	2.0	1.2	36.5	2.44
37	2.0	94	4.24	4.38	10.3	4.7*r	1.7	1.0	30.0	2.35
38	2.0	96	4.38	4.51	8.7	3.7*r	1.6	0.9	27.9	2.55
39	2.0	98	2.74	3.14	26.8	14.9*r	4.8	2.9	85.8	2.72
40	2.0	100	3.14	3.52	22.1	12.2*r	4.6	2.7	81.5	3.11
41	2.0	102	3.52	3.77	18.3	9.6*r	3.0	1.8	53.6	2.45
42	2.0	104	3.77	4.01	15.4	7.9*r	2.9	1.7	51.5	2.77
43	2.0	106	4.01	4.15	13.1	6.2*r	1.7	1.0	30.0	1.88
44	2.0	108	4.15	4.33	11.2	5.3*r	2.2	1.3	38.6	2.81
45	2.0	110	4.33	4.46	9.3	4*r	1.6	0.9	27.9	2.40
46	2.0	112	2.76	3.23	26.1	14.8*r	5.6	3.4	100.8	3.27
47	2.0	114	3.23	3.61	21.0	11.6*r	4.5	2.7	80.7	3.22
48	2.0	116	3.61	3.87	17.2	9*r	3.1	1.9	55.8	2.71
49	2.0	118	3.87	4.09	14.3	7.2*r	2.6	1.6	47.2	2.72
50	2.0	120	4.09	4.24	12.1	5.7*r	1.8	1.1	32.2	2.18
51	2.0	122	4.24	4.38	10.3	4.7*r	1.7	1.0	30.0	2.35
52	2.0	124	4.38	4.56	8.4	3.7*r	2.2	1.3	38.6	3.64
53	2.0	126	2.83	3.24	25.6	14.3*r	4.9	2.9	88.0	2.90
54	2.0	128	3.24	3.56	21.2	11.5*r	3.8	2.3	68.6	2.72
55	2.0	130	3.56	3.83	17.7	9.3*r	3.2	1.9	57.9	2.73
56	2.0	132	3.83	3.97	15.2	7.5*r	1.7	1.0	30.0	1.63
57	2.0	134	3.97	4.15	13.3	6.5*r	2.2	1.3	38.6	2.38
58	2.0	136	4.15	4.32	11.2	5.3*r	2.0	1.2	36.5	2.64
59	2.0	138	4.32	4.44	9.5	4.1*r	1.4	0.9	25.7	2.18
60	2.0	140	2.76	3.15	26.6	14.8*r	4.7	2.8	83.7	2.67

1: Porosity of gravel assumed to be 0.4 to correct drop in water.  
 \*Porchet method used to convert percolation rate to infiltration rate.


**Stabilized, Unfactored Infiltration Rate\*:** 2.69 inch/hour

<b>HCA Design and Construction</b> Riverside Community Hospital Riverside, California	<b>BOREHOLE PERCOLATION TEST I-1B</b> <b>INFILTRATION RATE</b>	PROJECT NUMBER <b>SD809</b>	FIGURE NUMBER <b>D-1.2a</b>
---	---	--------------------------------	--------------------------------

# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/2/2024</u>	Borehole Radius (*r): <u>2 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/3/2024</u>	Casing Diameter: <u>2 in.</u>
Test Hole Number: <u>I-1B</u>	Tested By: <u>DMG</u>	Depth of Hole: <u>5.2 ft</u>
Drilling Method: <u>Hand Auger</u>	Temperature <sup>3</sup> : <u>77 F</u>	Test Depth: <u>3½ to 4½ ft</u>

## UNFACTORED INFILTRATION RATES\* DURING TEST



**Preliminary Factored Infiltration Rate<sup>1</sup>: 1.08 in/hr**

**Feasibility Screening Factor of Safety, F.S.<sup>2</sup>: 2.0**

**Temperature Correction Factor<sup>2,3</sup>: 0.8**

Factored Infiltration Rate <sup>2</sup>	Design Condition <sup>2</sup>
Below 0.05	No Infiltration
0.05 to 0.50	Partial Infiltration
Above 0.50	Full Infiltration

\*Porchet method used to convert percolation rate to infiltration rate.  
 1: Rate Factored by Factor of Safety and Temperature Correction Factor.  
 2: Reference: Riverside Design Handbook for Low Impact Development BMP (2011).  
 3: Factor based on as-tested water temperature of 77 F and rainfall temperature of 60 F.

<b>HCA Design and Construction                  Riverside Community Hospital                  Riverside, California</b>	<b>BOREHOLE PERCOLATION TEST I-1B                  INFILTRATION RATE</b>	<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="font-size: small; text-align: center;">PROJECT NUMBER</td> <td style="font-size: small; text-align: center;">FIGURE NUMBER</td> </tr> <tr> <td style="font-size: large; font-weight: bold; text-align: center;">SD809</td> <td style="font-size: large; font-weight: bold; text-align: center;">D-1.2b</td> </tr> </table>	PROJECT NUMBER	FIGURE NUMBER	SD809	D-1.2b
PROJECT NUMBER	FIGURE NUMBER					
SD809	D-1.2b					

# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/1/2024</u>	Borehole Radius (*r): <u>4 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/4/2024</u>	Casing Diameter: <u>4 in.</u>
Test Hole Number: <u>I-2A</u>	Tested By: <u>DMG</u>	Depth of Hole: <u>8.0 ft</u>
Drilling Method: <u>Hollow Stem Auger</u>	Temperature: <u>65 F</u>	Gravel Base Thickness: <u>2 in.</u>

## DATA SHEET

Reading Number	Time Interval (min.)	Cumulative Time (min.)	Initial Depth to Water (ft.)	Final Depth to Water (ft.)	Avg. Height of Water above Gravel Base (in.)		Measured Drop in Water Level (in.)	Corrected Drop in Water Level <sup>1</sup> (in.)	Corrected Percolation Rate <sup>1</sup> (in./hour)	Unfactored Infiltration Rate* (in./hour)
					H <sub>avg</sub>	H <sub>int</sub>				
	Δt	T	[from ground surface]				ΔH	ΔH <sub>c</sub>	ΔH <sub>c</sub> /Δt	I <sub>t</sub>
6	1.0	6	6.50	6.88	15.8	4*r	4.6	2.5	150.5	16.9
7	1.0	7	6.88	7.11	12.1	2.9*r	2.8	1.5	91.1	12.9
8	1.0	8	7.11	7.53	8.2	2.2*r	5.0	2.8	166.3	32.6
9	1.0	9	3.78	4.34	47.3	12.2*r	6.7	3.7	221.8	8.99
10	1.0	10	4.34	4.68	41.9	10.5*r	4.1	2.2	134.6	6.13
11	1.0	11	4.68	4.93	38.4	9.5*r	3.0	1.7	99.0	4.90
12	1.0	12	5.22	5.62	31.0	7.9*r	4.8	2.6	158.4	9.60
13	1.0	13	5.62	6.21	25.1	6.7*r	7.1	3.9	233.6	17.27
14	1.0	14	6.21	6.40	20.4	4.9*r	2.3	1.3	75.2	6.72
15	2.0	16	3.72	4.37	47.5	12.4*r	7.8	4.3	128.7	5.20
16	2.0	18	4.37	4.41	43.4	10.4*r	0.5	0.3	7.9	0.35
17	2.0	20	4.41	4.65	41.7	10.3*r	2.9	1.6	47.5	2.18
18	2.0	22	4.65	4.78	39.5	9.6*r	1.6	0.9	25.7	1.24
19	2.0	24	4.78	4.97	37.5	9.2*r	2.3	1.3	37.6	1.90
20	2.0	26	4.97	5.13	35.4	8.6*r	1.9	1.1	31.7	1.69
21	2.0	28	5.13	5.61	31.6	8.1*r	5.8	3.2	95.0	5.66
22	2.0	30	5.61	6.13	25.6	6.7*r	6.2	3.4	103.0	7.46
23	2.0	32	6.13	6.33	21.3	5.1*r	2.4	1.3	39.6	3.40
24	5.0	37	3.79	4.37	47.1	12.1*r	7.0	3.8	45.9	1.87
25	5.0	42	4.37	4.76	41.3	10.4*r	4.7	2.6	30.9	1.43
26	5.0	47	4.76	5.13	36.7	9.2*r	4.4	2.4	29.3	1.51
27	5.0	52	5.13	6.19	28.1	8.1*r	12.7	7.0	84.0	5.57
28	5.0	57	3.83	4.37	46.8	12*r	6.5	3.6	42.8	1.75
29	5.0	62	4.37	4.76	41.3	10.4*r	4.7	2.6	30.9	1.43
30	5.0	67	4.76	5.17	36.5	9.2*r	4.9	2.7	32.5	1.69
31	5.0	72	5.17	6.29	27.3	8*r	13.4	7.4	88.7	6.06
32	5.0	77	3.97	4.50	45.2	11.6*r	6.4	3.5	42.0	1.78
33	5.0	82	4.50	4.90	39.6	10*r	4.8	2.6	31.7	1.52
34	5.0	87	4.90	5.70	32.4	8.8*r	9.6	5.3	63.4	3.68
35	5.0	92	5.70	6.55	22.5	6.4*r	10.2	5.6	67.3	5.49
36	5.0	97	4.05	4.56	44.4	11.4*r	6.1	3.4	40.4	1.74
37	5.0	102	4.56	4.96	38.9	9.8*r	4.8	2.6	31.7	1.55
38	5.0	107	4.96	6.01	30.2	8.6*r	12.6	6.9	83.2	5.16
39	5.0	112	6.01	6.51	20.9	5.5*r	6.0	3.3	39.6	3.46
40	5.0	117	4.05	4.52	44.6	11.4*r	5.6	3.1	37.2	1.60
41	5.0	122	4.52	4.88	39.6	10*r	4.3	2.4	28.5	1.37

1: Porosity of gravel assumed to be 0.4 to correct drop in water.  
 \*Porchet method used to convert percolation rate to infiltration rate.


**Stabilized, Unfactored Infiltration Rate\*:** 2.92 inch/hour

<b>HCA Design and Construction                  Riverside Community Hospital                  Riverside, California</b>	<b>BOREHOLE PERCOLATION TEST I-2A                  INFILTRATION RATE</b>	<b>GROUP DELTA</b> <small>PROJECT NUMBER</small> <b>SD809</b>
		<small>FIGURE NUMBER</small> <b>D-2.1a</b>

# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/1/2024</u>	Borehole Radius (*r): <u>4 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/4/2024</u>	Casing Diameter: <u>4 in.</u>
Test Hole Number: <u>I-2A</u>	Tested By: <u>DMG</u>	Depth of Hole: <u>8.0 ft</u>
Drilling Method: <u>Hollow Stem Auger</u>	Temperature <sup>3</sup> : <u>65 F</u>	Test Depth: <u>7½ to 8½ ft</u>

## UNFACTORED INFILTRATION RATES\* DURING TEST



**Preliminary Factored Infiltration Rate<sup>1</sup>: 1.36 in/hr**

**Feasibility Screening Factor of Safety, F.S.<sup>2</sup>: 2.0**

**Temperature Correction Factor<sup>2,3</sup>: 0.93**

Factored Infiltration Rate <sup>2</sup>	Design Condition <sup>2</sup>
Below 0.05	No Infiltration
0.05 to 0.50	Partial Infiltration
Above 0.50	Full Infiltration

\*Porchet method used to convert percolation rate to infiltration rate.  
 1: Rate Factored by Factor of Safety and Temperature Correction Factor.  
 2: Reference: Riverside Design Handbook for Low Impact Development BMP (2011).  
 3: Factor based on as-tested water temperature of 65 F and rainfall temperature of 60 F.

<b>HCA Design and Construction Riverside Community Hospital Riverside, California</b>	<b>BOREHOLE PERCOLATION TEST I-2A INFILTRATION RATE</b>	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="font-size: small;">PROJECT NUMBER</td> <td style="font-size: small;">FIGURE NUMBER</td> </tr> <tr> <td style="text-align: center;"><b>SD809</b></td> <td style="text-align: center;"><b>D-2.1b</b></td> </tr> </table>	PROJECT NUMBER	FIGURE NUMBER	<b>SD809</b>	<b>D-2.1b</b>
PROJECT NUMBER	FIGURE NUMBER					
<b>SD809</b>	<b>D-2.1b</b>					

# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/1/2024</u>	Borehole Radius (*r): <u>4 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/4/2024</u>	Casing Diameter: <u>4 in.</u>
Test Hole Number: <u>I-2B</u>	Tested By: <u>DMG</u>	Depth of Hole: <u>8.0 ft</u>
Drilling Method: <u>Hollow Stem Auger</u>	Temperature: <u>60 F</u>	Gravel Base Thickness: <u>2 in.</u>

## DATA SHEET

Reading Number	Time Interval (min.)	Cumulative Time (min.)	Initial Depth to Water (ft.)	Final Depth to Water (ft.)	Avg. Height of Water above Gravel Base (in.)		Measured Drop in Water Level (in.)	Corrected Drop in Water Level <sup>1</sup> (in.)	Corrected Percolation Rate <sup>1</sup> (in./hour)	Unfactored Infiltration Rate* (in./hour)
					H <sub>avg</sub>	H <sub>int</sub>				
	$\Delta t$	T	[from ground surface]				$\Delta H$	$\Delta H_c$	$\Delta H_c / \Delta t$	I <sub>t</sub>
1	1.0	1	4.19	4.77	42.3	10.9*r	7.0	3.8	229.7	10.4
2	1.0	2	4.77	5.65	33.5	9.2*r	10.6	5.8	348.5	19.6
8	2.0	4	3.69	4.21	48.6	12.4*r	6.2	3.4	103.0	4.07
9	2.0	6	4.21	4.57	43.4	10.9*r	4.3	2.4	71.3	3.14
10	2.0	8	4.57	5.13	37.8	9.8*r	6.7	3.7	110.9	5.57
11	2.0	10	5.13	5.65	31.4	8.1*r	6.2	3.4	103.0	6.17
12	2.0	12	5.65	5.98	26.3	6.6*r	4.0	2.2	65.3	4.62
13	2.0	14	5.98	6.21	22.9	5.6*r	2.8	1.5	45.5	3.66
14	5.0	19	3.67	4.42	47.5	12.5*r	9.0	5.0	59.4	2.40
15	5.0	24	4.42	5.51	36.5	10.3*r	13.1	7.2	86.3	4.49
16	5.0	29	5.51	6.03	26.8	7*r	6.2	3.4	41.2	2.86
17	5.0	34	6.03	6.47	21.0	5.4*r	5.3	2.9	34.8	3.03
18	5.0	39	3.66	4.32	48.2	12.5*r	7.9	4.4	52.3	2.08
19	5.0	44	4.32	5.19	39.0	10.6*r	10.4	5.7	68.9	3.36
20	5.0	49	5.19	5.83	29.9	7.9*r	7.7	4.2	50.7	3.18
21	5.0	54	5.83	6.25	23.6	6*r	5.0	2.8	33.3	2.60
22	5.0	59	3.77	4.31	47.6	12.2*r	6.5	3.6	42.8	1.73
23	5.0	64	4.31	5.09	39.6	10.6*r	9.4	5.1	61.8	2.97
24	5.0	69	5.09	5.81	30.6	8.2*r	8.6	4.8	57.0	3.49
25	5.0	74	5.81	6.22	23.9	6.1*r	4.9	2.7	32.5	2.51
26	5.0	79	3.88	4.34	46.7	11.9*r	5.5	3.0	36.4	1.50
27	5.0	84	4.34	5.06	39.6	10.5*r	8.6	4.8	57.0	2.74
28	5.0	89	5.06	5.72	31.4	8.3*r	7.9	4.4	52.3	3.13
29	5.0	94	5.72	6.14	24.9	6.4*r	5.0	2.8	33.3	2.48
30	5.0	99	6.14	6.43	20.6	5.1*r	3.5	1.9	23.0	2.03

1: Porosity of gravel assumed to be 0.4 to correct drop in water.  
 \*Porchet method used to convert percolation rate to infiltration rate.

**Stabilized, Unfactored Infiltration Rate\*: 2.63 inch/hour**


<b>HCA Design and Construction Riverside Community Hospital Riverside, California</b>	<b>BOREHOLE PERCOLATION TEST I-2B INFILTRATION RATE</b>	 <small>PROJECT NUMBER</small> <b>SD809</b>
		<small>FIGURE NUMBER</small> <b>D-2.2a</b>



# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/1/2024</u>	Borehole Radius (*r): <u>4 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/4/2024</u>	Casing Diameter: <u>4 in.</u>
Test Hole Number: <u>I-2B</u>	Tested By: <u>DMG</u>	Depth of Hole: <u>8.0 ft</u>
Drilling Method: <u>Hollow Stem Auger</u>	Temperature <sup>3</sup> : <u>60 F</u>	Test Depth: <u>7½ to 8½ ft</u>

## UNFACTORED INFILTRATION RATES\* DURING TEST



**Preliminary Factored Infiltration Rate<sup>1</sup>: 1.32 in/hr**

**Feasibility Screening Factor of Safety, F.S.<sup>2</sup>: 2.0**

**Temperature Correction Factor<sup>2,3</sup>: 1**

Factored Infiltration Rate <sup>2</sup>	Design Condition <sup>2</sup>
Below 0.05	No Infiltration
0.05 to 0.50	Partial Infiltration
Above 0.50	Full Infiltration

\*Porchet method used to convert percolation rate to infiltration rate.  
 1: Rate Factored by Factor of Safety and Temperature Correction Factor.  
 2: Reference: Riverside Design Handbook for Low Impact Development BMP (2011).  
 3: Factor based on as-tested water temperature of 60 F and rainfall temperature of 60 F.

<b>HCA Design and Construction                  Riverside Community Hospital                  Riverside, California</b>	<b>BOREHOLE PERCOLATION TEST I-2B                  INFILTRATION RATE</b>	<b>GROUP DELTA</b> <small>PROJECT NUMBER</small> <b>SD809</b>
		<small>FIGURE NUMBER</small> <b>D-2.2b</b>

# BOREHOLE PERCOLATION TEST

**Project Name:** Riverside Hospital                      **Date Drilled:** 4/3/2024                      **Borehole Radius (\*r):** 2 in.  
**Project Number:** SD809                                      **Date Tested:** 4/4/2024                                      **Casing Diameter:** 2 in.  
**Test Hole Number:** I-3A                                      **Tested By:** DMG    **Depth of Hole:** 5.3 ft  
**Drilling Method:** Hand Auger                              **Temperature:** 70 F    **Gravel Base Thickness:** 3 in.

## DATA SHEET

Reading Number	Time Interval (min.)	Cumulative Time (min.)	Initial Depth to Water (ft.)	Final Depth to Water (ft.)	Avg. Height of Water above Gravel Base (in.)		Measured Drop in Water Level (in.)	Corrected Drop in Water Level <sup>1</sup> (in.)	Corrected Percolation Rate <sup>1</sup> (in./hour)	Unfactored Infiltration Rate* (in./hour)
					H <sub>avg</sub>	H <sub>int</sub>				
	$\Delta t$	T	[from ground surface]				$\Delta H$	$\Delta H_c$	$\Delta H_c / \Delta t$	I <sub>t</sub>
1	24.0	24	1.80	2.30	38.4	22*r	6.0	3.6	8.9	0.20
2	25.0	49	2.30	2.75	32.7	18.5*r	5.4	3.2	7.7	0.20
3	10.0	59	2.75	2.94	28.9	15.5*r	2.3	1.4	8.2	0.24
4	10.0	69	2.94	3.06	27.0	14.1*r	1.4	0.9	5.1	0.16
5	10.0	79	3.06	3.24	25.2	13.3*r	2.2	1.3	7.7	0.26
6	10.0	89	3.24	3.38	23.3	12.1*r	1.7	1.0	6.0	0.22
7	10.0	99	3.38	3.44	22.1	11.1*r	0.7	0.4	2.6	0.10
8	10.0	109	3.44	3.55	21.1	10.7*r	1.3	0.8	4.7	0.19
9	10.0	119	3.55	3.68	19.7	10*r	1.6	0.9	5.6	0.24
10	10.0	129	3.68	3.74	18.5	9.1*r	0.7	0.4	2.6	0.12


1: Porosity of gravel assumed to be 0.4 to correct drop in water.                      **Stabilized, Unfactored Infiltration Rate\*:** **0.19 inch/hour**  
 \*Porchet method used to convert percolation rate to infiltration rate.

<b>HCA Design and Construction</b> <b>Riverside Community Hospital</b> <b>Riverside, California</b>	<b>BOREHOLE PERCOLATION TEST I-3A</b> <b>INFILTRATION RATE</b>	 <small>PROJECT NUMBER</small> <b>SD809</b>	<small>FIGURE NUMBER</small> <b>D-3.1a</b>
---	---	---	---

# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/3/2024</u>	Borehole Radius (*r): <u>2 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/4/2024</u>	Casing Diameter: <u>2 in.</u>
Test Hole Number: <u>I-3A</u>	Tested By: <u>DMG</u>	Depth of Hole: <u>5.3 ft</u>
Drilling Method: <u>Hand Auger</u>	Temperature <sup>3</sup> : <u>70 F</u>	Test Depth: <u>2½ to 3½ ft</u>

## UNFACTORED INFILTRATION RATES\* DURING TEST



**Preliminary Factored Infiltration Rate<sup>1</sup>: 0.08 in/hr**

**Feasibility Screening Factor of Safety, F.S.<sup>2</sup>: 2.0**

**Temperature Correction Factor<sup>2,3</sup>: 0.87**

Factored Infiltration Rate <sup>2</sup>	Design Condition <sup>2</sup>
Below 0.05	No Infiltration
0.05 to 0.50	Partial Infiltration
Above 0.50	Full Infiltration

\*Porchet method used to convert percolation rate to infiltration rate.  
 1: Rate Factored by Factor of Safety and Temperature Correction Factor.  
 2: Reference: Riverside Design Handbook for Low Impact Development BMP (2011).  
 3: Factor based on as-tested water temperature of 70 F and rainfall temperature of 60 F.

<b>HCA Design and Construction</b> Riverside Community Hospital Riverside, California	<b>BOREHOLE PERCOLATION TEST I-3A</b> <b>INFILTRATION RATE</b>	PROJECT NUMBER <b>SD809</b>	FIGURE NUMBER <b>D-3.1b</b>
---	---	--------------------------------	--------------------------------

## BOREHOLE PERCOLATION TEST

Project Name: Riverside Hospital  
 Project Number: SD809  
 Test Hole Number: I-3B  
 Drilling Method: Hand Auger

Date Drilled: 4/3/2024  
 Date Tested: 4/4/2024  
 Tested By: DMG  
 Temperature: 70 F

Borehole Radius (\*r): 2 in.  
 Casing Diameter: 2 in.  
 Depth of Hole: 5.3 ft  
 Gravel Base Thickness: 3 in.

### DATA SHEET

Reading Number	Time Interval (min.)	Cumulative Time (min.)	Initial Depth to Water (ft.)	Final Depth to Water (ft.)	Avg. Height of Water above Gravel Base (in.)		Measured Drop in Water Level (in.)	Corrected Drop in Water Level <sup>1</sup> (in.)	Corrected Percolation Rate <sup>1</sup> (in./hour)	Unfactored Infiltration Rate* (in./hour)
	$\Delta t$	T	[from ground surface]		$H_{avg}$	$H_{int}$	$\Delta H$	$\Delta H_c$	$\Delta H_c / \Delta t$	$I_t$
1	25.0	25	2.98	3.03	27.0	13.9*r	0.6	0.4	0.9	0.03
2	25.0	50	3.03	3.15	26.0	13.5*r	1.4	0.9	2.1	0.07
3	10.0	60	3.15	3.17	25.1	12.7*r	0.2	0.1	0.9	0.03
4	10.0	70	3.17	3.21	24.8	12.6*r	0.5	0.3	1.7	0.06
5	10.0	80	3.21	3.22	24.5	12.3*r	0.1	0.1	0.4	0.01
6	10.0	90	3.22	3.26	24.2	12.2*r	0.5	0.3	1.7	0.06
7	10.0	100	3.26	3.27	23.9	12*r	0.1	0.1	0.4	0.02
8	10.0	110	3.27	3.28	23.7	11.9*r	0.1	0.1	0.4	0.02
9	10.0	120	3.28	3.30	23.6	11.8*r	0.2	0.1	0.9	0.03
10	10.0	130	3.30	3.34	23.2	11.7*r	0.5	0.3	1.7	0.06

1: Porosity of gravel assumed to be 0.4 to correct drop in water.  
 \*Porchet method used to convert percolation rate to infiltration rate.


**Stabilized, Unfactored  
 Infiltration Rate\*:** 0.04 inch/hour

HCA Design and Construction Riverside Community Hospital Riverside, California	<b>BOREHOLE PERCOLATION TEST I-3B                  INFILTRATION RATE</b>	<b>GROUP DELTA</b>	
		PROJECT NUMBER <b>SD809</b>	FIGURE NUMBER <b>D-3.2a</b>

# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/3/2024</u>	Borehole Radius (*r): <u>2 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/4/2024</u>	Casing Diameter: <u>2 in.</u>
Test Hole Number: <u>I-3B</u>	Tested By: <u>DMG</u>	Depth of Hole: <u>5.3 ft</u>
Drilling Method: <u>Hand Auger</u>	Temperature <sup>3</sup> : <u>70 F</u>	Test Depth: <u>3 to 3½ ft</u>

## UNFACTORED INFILTRATION RATES\* DURING TEST



**Preliminary Factored Infiltration Rate<sup>1</sup>: 0.02 in/hr**

**Feasibility Screening Factor of Safety, F.S.<sup>2</sup>: 2.0**

**Temperature Correction Factor<sup>2,3</sup>: 0.87**

Factored Infiltration Rate <sup>2</sup>	Design Condition <sup>2</sup>
Below 0.05	No Infiltration
0.05 to 0.50	Partial Infiltration
Above 0.50	Full Infiltration

\*Porchet method used to convert percolation rate to infiltration rate.  
 1: Rate Factored by Factor of Safety and Temperature Correction Factor.  
 2: Reference: Riverside Design Handbook for Low Impact Development BMP (2011).  
 3: Factor based on as-tested water temperature of 70 F and rainfall temperature of 60 F.


<b>HCA Design and Construction                  Riverside Community Hospital                  Riverside, California</b>	<b>BOREHOLE PERCOLATION TEST I-3B                  INFILTRATION RATE</b>	<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="font-size: small; text-align: center;">PROJECT NUMBER</td> <td style="font-size: small; text-align: center;">FIGURE NUMBER</td> </tr> <tr> <td style="text-align: center; font-weight: bold; font-size: large;">SD809</td> <td style="text-align: center; font-weight: bold; font-size: large;">D-3.2b</td> </tr> </table>	PROJECT NUMBER	FIGURE NUMBER	SD809	D-3.2b
PROJECT NUMBER	FIGURE NUMBER					
SD809	D-3.2b					



# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/2/2024</u>	Borehole Radius (*r): <u>2 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/3/2024</u>	Casing Diameter: <u>2 in.</u>
Test Hole Number: <u>I-4A</u>	Tested By: <u>JWJ</u>	Depth of Hole: <u>4.8 ft</u>
Drilling Method: <u>Hand Auger</u>	Temperature <sup>3</sup> : <u>70 F</u>	Test Depth: <u>2½ to 3½ ft</u>

## UNFACTORED INFILTRATION RATES\* DURING TEST



**Preliminary Factored Infiltration Rate<sup>1</sup>: 0.08 in/hr**

**Feasibility Screening Factor of Safety, F.S.<sup>2</sup>: 2.0**

**Temperature Correction Factor<sup>2,3</sup>: 0.87**

Factored Infiltration Rate <sup>2</sup>	Design Condition <sup>2</sup>
Below 0.05	No Infiltration
0.05 to 0.50	Partial Infiltration
Above 0.50	Full Infiltration

\*Porchet method used to convert percolation rate to infiltration rate.  
 1: Rate Factored by Factor of Safety and Temperature Correction Factor.  
 2: Reference: Riverside Design Handbook for Low Impact Development BMP (2011).  
 3: Factor based on as-tested water temperature of 70 F and rainfall temperature of 60 F.

<b>HCA Design and Construction                  Riverside Community Hospital                  Riverside, California</b>	<b>BOREHOLE PERCOLATION TEST I-4A                  INFILTRATION RATE</b>	<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="font-size: small;">PROJECT NUMBER</td> <td style="font-size: small;">FIGURE NUMBER</td> </tr> <tr> <td style="font-weight: bold; font-size: large;">SD809</td> <td style="font-weight: bold; font-size: large;">D-4.1b</td> </tr> </table>	PROJECT NUMBER	FIGURE NUMBER	SD809	D-4.1b
PROJECT NUMBER	FIGURE NUMBER					
SD809	D-4.1b					

# BOREHOLE PERCOLATION TEST


Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/2/2024</u>	Borehole Radius (*r): <u>2 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/3/2024</u>	Casing Diameter: <u>2 in.</u>
Test Hole Number: <u>I-4B</u>	Tested By: <u>JWJ</u>	Depth of Hole: <u>5.0 ft</u>
Drilling Method: <u>Hand Auger</u>	Temperature: <u>70 F</u>	Gravel Base Thickness: <u>2 in.</u>

## DATA SHEET

Reading Number	Time Interval (min.)	Cumulative Time (min.)	Initial Depth to Water (ft.)	Final Depth to Water (ft.)	Avg. Height of Water above Gravel Base (in.)		Measured Drop in Water Level (in.)	Corrected Drop in Water Level <sup>1</sup> (in.)	Corrected Percolation Rate <sup>1</sup> (in./hour)	Unfactored Infiltration Rate* (in./hour)
					H <sub>avg</sub>	H <sub>int</sub>				
	Δt	T	[from ground surface]				ΔH	ΔH <sub>c</sub>	ΔH <sub>c</sub> /Δt	I <sub>t</sub>
1	6.0	6	0.97	1.47	45.4	26.5*r	6.0	3.6	35.8	0.68
2	6.0	12	1.07	1.62	43.9	25.8*r	6.6	3.9	39.3	0.77
3	10.0	22	2.47	3.02	27.1	16.2*r	6.6	3.9	23.6	0.74
4	10.0	32	2.72	3.11	25.1	14.5*r	4.7	2.8	16.7	0.56
5	10.0	42	2.62	2.98	26.4	15.2*r	4.3	2.6	15.4	0.49
6	10.0	52	2.64	3.01	26.1	15.1*r	4.4	2.6	15.9	0.51
7	10.0	62	2.52	2.87	27.7	15.9*r	4.2	2.5	15.0	0.46
8	10.0	72	2.73	3.17	24.6	14.4*r	5.3	3.1	18.9	0.65
9	10.0	82	2.77	3.17	24.4	14.2*r	4.8	2.9	17.2	0.59
10	10.0	92	2.78	3.21	24.1	14.1*r	5.2	3.1	18.4	0.65
11	10.0	102	2.58	2.87	27.3	15.5*r	3.5	2.1	12.4	0.39
12	10.0	112	2.69	3.09	25.4	14.7*r	4.8	2.9	17.2	0.57
13	10.0	122	2.67	2.97	26.2	14.9*r	3.6	2.1	12.9	0.42
14	10.0	132	2.71	3.10	25.2	14.6*r	4.7	2.8	16.7	0.56

**Stabilized, Unfactored Infiltration Rate\*: 0.54 inch/hour**

1: Porosity of gravel assumed to be 0.4 to correct drop in water.  
\*Porchet method used to convert percolation rate to infiltration rate.


<b>HCA Design and Construction</b> <b>Riverside Community Hospital</b> <b>Riverside, California</b>	<b>BOREHOLE PERCOLATION TEST I-4B</b> <b>INFILTRATION RATE</b>	 <b>GROUP DELTA</b>	PROJECT NUMBER <b>SD809</b>	FIGURE NUMBER <b>D-4.2a</b>
---	---	---	--------------------------------	--------------------------------



# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/2/2024</u>	Borehole Radius (*r): <u>2 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/3/2024</u>	Casing Diameter: <u>2 in.</u>
Test Hole Number: <u>I-4B</u>	Tested By: <u>JWJ</u>	Depth of Hole: <u>5.0 ft</u>
Drilling Method: <u>Hand Auger</u>	Temperature <sup>3</sup> : <u>70 F</u>	Test Depth: <u>2½ to 3½ ft</u>

## UNFACTORED INFILTRATION RATES\* DURING TEST



**Preliminary Factored Infiltration Rate<sup>1</sup>: 0.23 in/hr**

**Feasibility Screening Factor of Safety, F.S.<sup>2</sup>: 2.0**

**Temperature Correction Factor<sup>2,3</sup>: 0.87**

Factored Infiltration Rate <sup>2</sup>	Design Condition <sup>2</sup>
Below 0.05	No Infiltration
0.05 to 0.50	Partial Infiltration
Above 0.50	Full Infiltration

\*Porchet method used to convert percolation rate to infiltration rate.  
 1: Rate Factored by Factor of Safety and Temperature Correction Factor.  
 2: Reference: Riverside Design Handbook for Low Impact Development BMP (2011).  
 3: Factor based on as-tested water temperature of 70 F and rainfall temperature of 60 F.


<b>HCA Design and Construction</b> <b>Riverside Community Hospital</b> <b>Riverside, California</b>	<b>BOREHOLE PERCOLATION TEST I-4B</b> <b>INFILTRATION RATE</b>	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="font-size: small;">PROJECT NUMBER</td> <td style="font-size: small;">FIGURE NUMBER</td> </tr> <tr> <td style="text-align: center;"><b>SD809</b></td> <td style="text-align: center;"><b>D-4.2b</b></td> </tr> </table>	PROJECT NUMBER	FIGURE NUMBER	<b>SD809</b>	<b>D-4.2b</b>
PROJECT NUMBER	FIGURE NUMBER					
<b>SD809</b>	<b>D-4.2b</b>					



# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/2/2024</u>	Borehole Radius (*r): <u>2 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/5/2024</u>	Casing Diameter: <u>2 in.</u>
Test Hole Number: <u>I-5A</u>	Tested By: <u>JWJ</u>	Depth of Hole: <u>3.1 ft</u>
Drilling Method: <u>Hand Auger</u>	Temperature <sup>3</sup> : <u>64 F</u>	Test Depth: <u>2 to 3 ft</u>

## UNFACTORED INFILTRATION RATES\* DURING TEST



**Preliminary Factored Infiltration Rate<sup>1</sup>: 0.04 in/hr**

**Feasibility Screening Factor of Safety, F.S.<sup>2</sup>: 2.0**

**Temperature Correction Factor<sup>2,3</sup>: 0.95**

Factored Infiltration Rate <sup>2</sup>	Design Condition <sup>2</sup>
Below 0.05	No Infiltration
0.05 to 0.50	Partial Infiltration
Above 0.50	Full Infiltration

\*Porchet method used to convert percolation rate to infiltration rate.  
 1: Rate Factored by Factor of Safety and Temperature Correction Factor.  
 2: Reference: Riverside Design Handbook for Low Impact Development BMP (2011).  
 3: Factor based on as-tested water temperature of 64 F and rainfall temperature of 60 F.

<b>HCA Design and Construction</b> Riverside Community Hospital Riverside, California	<b>BOREHOLE PERCOLATION TEST I-5A</b> <b>INFILTRATION RATE</b>	<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="font-size: small;">PROJECT NUMBER</td> <td style="font-size: small;">FIGURE NUMBER</td> </tr> <tr> <td style="font-weight: bold; font-size: large;">SD809</td> <td style="font-weight: bold; font-size: large;">D-5.1b</td> </tr> </table>	PROJECT NUMBER	FIGURE NUMBER	SD809	D-5.1b
PROJECT NUMBER	FIGURE NUMBER					
SD809	D-5.1b					

# BOREHOLE PERCOLATION TEST


Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/2/2024</u>	Borehole Radius (*r): <u>2 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/5/2024</u>	Casing Diameter: <u>2 in.</u>
Test Hole Number: <u>I-5B</u>	Tested By: <u>JWJ</u>	Depth of Hole: <u>3.0 ft</u>
Drilling Method: <u>Hand Auger</u>	Temperature: <u>64 F</u>	Gravel Base Thickness: <u>3 in.</u>

## DATA SHEET

Reading Number	Time Interval (min.)	Cumulative Time (min.)	Initial Depth to Water (ft.)	Final Depth to Water (ft.)	Avg. Height of Water above Gravel Base (in.)		Measured Drop in Water Level (in.)	Corrected Drop in Water Level <sup>1</sup> (in.)	Corrected Percolation Rate <sup>1</sup> (in./hour)	Unfactored Infiltration Rate* (in./hour)
					H <sub>avg</sub>	H <sub>int</sub>				
	Δt	T	[from ground surface]				ΔH	ΔH <sub>c</sub>	ΔH <sub>c</sub> /Δt	I <sub>t</sub>
1	10.0	10	0.93	0.94	24.7	12.5*r	0.1	0.1	0.4	0.01
2	10.0	20	0.94	0.96	24.6	12.4*r	0.2	0.1	0.9	0.03
3	10.0	30	0.96	0.97	24.4	12.3*r	0.1	0.1	0.4	0.01
4	10.0	40	0.97	0.99	24.2	12.2*r	0.2	0.1	0.9	0.03
5	10.0	50	0.99	1.02	23.9	12*r	0.4	0.2	1.3	0.05
6	10.0	60	1.02	1.05	23.5	11.8*r	0.4	0.2	1.3	0.05
7	10.0	70	1.05	1.07	23.2	11.6*r	0.2	0.1	0.9	0.03
8	10.0	80	0.97	0.99	24.2	12.2*r	0.2	0.1	0.9	0.03
9	10.0	90	0.99	1.01	24.0	12*r	0.2	0.1	0.9	0.03
10	10.0	100	1.00	1.02	23.8	12*r	0.2	0.1	0.9	0.03
11	10.0	110	1.02	1.04	23.6	11.8*r	0.2	0.1	0.9	0.03
12	10.0	120	1.04	1.06	23.4	11.7*r	0.2	0.1	0.9	0.03

1: Porosity of gravel assumed to be 0.4 to correct drop in water.  
 \*Porchet method used to convert percolation rate to infiltration rate.


**Stabilized, Unfactored Infiltration Rate\*: 0.03 inch/hour**

<b>HCA Design and Construction          Riverside Community Hospital          Riverside, California</b>	<b>BOREHOLE PERCOLATION TEST I-5B          INFILTRATION RATE</b>		<b>GROUP DELTA</b> <small>PROJECT NUMBER</small> <b>SD809</b>	<small>FIGURE NUMBER</small> <b>D-5.2a</b>
---	--	---	---	---

# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/2/2024</u>	Borehole Radius (*r): <u>2 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/5/2024</u>	Casing Diameter: <u>2 in.</u>
Test Hole Number: <u>I-5B</u>	Tested By: <u>JWJ</u>	Depth of Hole: <u>3.0 ft</u>
Drilling Method: <u>Hand Auger</u>	Temperature <sup>3</sup> : <u>64 F</u>	Test Depth: <u>2 to 3 ft</u>

## UNFACTORED INFILTRATION RATES\* DURING TEST



**Preliminary Factored Infiltration Rate<sup>1</sup>: 0.02 in/hr**

**Feasibility Screening Factor of Safety, F.S.<sup>2</sup>: 2.0**

**Temperature Correction Factor<sup>2,3</sup>: 0.95**

Factored Infiltration Rate <sup>2</sup>	Design Condition <sup>2</sup>
Below 0.05	No Infiltration
0.05 to 0.50	Partial Infiltration
Above 0.50	Full Infiltration

\*Porchet method used to convert percolation rate to infiltration rate.  
 1: Rate Factored by Factor of Safety and Temperature Correction Factor.  
 2: Reference: Riverside Design Handbook for Low Impact Developmnet BMP (2011).  
 3: Factor based on as-tested water temperature of 64 F and rainfall temperature of 60 F.

<b>HCA Design and Construction Riverside Community Hospital Riverside, California</b>	<b>BOREHOLE PERCOLATION TEST I-5B INFILTRATION RATE</b>	<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="font-size: small;">PROJECT NUMBER</td> <td style="font-size: small;">FIGURE NUMBER</td> </tr> <tr> <td style="font-weight: bold; font-size: large;">SD809</td> <td style="font-weight: bold; font-size: large;">D-5.2b</td> </tr> </table>	PROJECT NUMBER	FIGURE NUMBER	SD809	D-5.2b
PROJECT NUMBER	FIGURE NUMBER					
SD809	D-5.2b					

# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/2/2024</u>	Borehole Radius (*r): <u>2 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/3/2024</u>	Casing Diameter: <u>2 in.</u>
Test Hole Number: <u>I-6A</u>	Tested By: <u>DMG</u>	Depth of Hole: <u>5.2 ft</u>
Drilling Method: <u>Hand Auger</u>	Temperature: <u>71 F</u>	Gravel Base Thickness: <u>2 in.</u>

## DATA SHEET

Reading Number	Time Interval (min.)	Cumulative Time (min.)	Initial Depth to Water (ft.)	Final Depth to Water (ft.)	Avg. Height of Water above Gravel Base (in.)		Measured Drop in Water Level (in.)	Corrected Drop in Water Level <sup>1</sup> (in.)	Corrected Percolation Rate <sup>1</sup> (in./hour)	Unfactored Infiltration Rate* (in./hour)
					H <sub>avg</sub>	H <sub>int</sub>				
	Δt	T	[from ground surface]				ΔH	ΔH <sub>c</sub>	ΔH <sub>c</sub> /Δt	I <sub>t</sub>
10	2.0	23	3.35	3.66	19.9	11.3*r	3.7	2.2	66.5	2.80
11	2.0	25	3.66	3.93	16.5	9.2*r	3.2	1.9	57.9	2.92
12	2.0	27	3.93	4.12	13.7	7.3*r	2.3	1.4	40.8	2.45
13	2.0	29	4.12	4.27	11.7	6*r	1.8	1.1	32.2	2.25
14	2.0	31	2.60	2.96	28.6	16.5*r	4.3	2.6	77.2	2.29
15	2.0	33	2.96	3.32	24.3	14*r	4.3	2.6	77.2	2.68
16	2.0	35	3.32	3.59	20.5	11.5*r	3.2	1.9	57.9	2.37
17	2.0	37	3.59	3.86	17.3	9.7*r	3.2	1.9	57.9	2.79
18	2.0	39	3.86	4.04	14.6	7.8*r	2.2	1.3	38.6	2.18
19	2.0	41	4.04	4.20	12.6	6.6*r	1.9	1.1	34.3	2.24
20	2.0	43	2.88	3.24	25.3	14.5*r	4.3	2.6	77.2	2.58
21	2.0	45	3.24	3.49	21.6	12.1*r	3.0	1.8	53.6	2.09
22	2.0	47	3.49	3.70	18.9	10.4*r	2.5	1.5	45.1	2.00
23	2.0	49	3.70	3.87	16.6	8.9*r	2.0	1.2	36.5	1.83
24	2.0	51	3.87	4.04	14.5	7.7*r	2.0	1.2	36.5	2.07
25	2.0	53	4.04	4.17	12.7	6.6*r	1.6	0.9	27.9	1.79
26	2.0	55	4.17	4.29	11.2	5.7*r	1.4	0.9	25.7	1.86
27	2.0	57	2.80	3.20	26.0	15.1*r	4.8	2.9	85.8	2.79
28	2.0	59	3.20	3.42	22.3	12.3*r	2.6	1.6	47.2	1.78
29	2.0	61	3.42	3.64	19.6	10.8*r	2.6	1.6	47.2	2.01
30	2.0	63	3.64	3.81	17.3	9.3*r	2.0	1.2	36.5	1.76
31	2.0	65	3.81	3.95	15.4	8.2*r	1.7	1.0	30.0	1.61
32	2.0	67	3.95	4.13	13.5	7.2*r	2.2	1.3	38.6	2.35
33	2.0	69	4.13	4.22	11.9	6*r	1.1	0.6	19.3	1.32
34	2.0	71	4.22	4.35	10.6	5.3*r	1.6	0.9	27.9	2.13
35	5.0	76	2.85	3.48	24.0	14.7*r	7.6	4.5	54.1	1.90
36	5.0	81	3.48	3.85	18.0	10.4*r	4.4	2.6	31.8	1.47
37	5.0	86	3.85	4.18	13.8	7.9*r	4.0	2.4	28.3	1.69
38	5.0	91	4.18	4.41	10.5	5.6*r	2.8	1.6	19.7	1.52
39	5.0	96	2.74	3.36	25.4	15.5*r	7.4	4.4	53.2	1.77
40	5.0	101	3.36	3.79	19.1	11.2*r	5.2	3.1	36.9	1.62
41	5.0	106	3.79	4.09	14.7	8.3*r	3.6	2.1	25.7	1.44
42	5.0	111	4.09	4.35	11.4	6.2*r	3.1	1.9	22.3	1.60
43	5.0	116	2.87	3.42	24.3	14.6*r	6.6	3.9	47.2	1.64
44	5.0	121	3.42	3.83	18.5	10.8*r	4.9	2.9	35.2	1.59
45	5.0	126	3.83	4.11	14.4	8*r	3.4	2.0	24.0	1.38

1: Porosity of gravel assumed to be 0.4 to correct drop in water.  
 \*Porchet method used to convert percolation rate to infiltration rate.


**Stabilized, Unfactored Infiltration Rate\*:** 1.60 inch/hour

<b>HCA Design and Construction</b> Riverside Community Hospital Riverside, California	<b>BOREHOLE PERCOLATION TEST I-6A</b> <b>INFILTRATION RATE</b>	<b>GROUP DELTA</b> PROJECT NUMBER: <b>SD809</b> FIGURE NUMBER: <b>D-6.1a</b>
---	---	--

# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/2/2024</u>	Borehole Radius (*r): <u>2 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/3/2024</u>	Casing Diameter: <u>2 in.</u>
Test Hole Number: <u>I-6A</u>	Tested By: <u>DMG</u>	Depth of Hole: <u>5.2 ft</u>
Drilling Method: <u>Hand Auger</u>	Temperature <sup>3</sup> : <u>71 F</u>	Test Depth: <u>7½ to 8½ ft</u>

## UNFACTORED INFILTRATION RATES\* DURING TEST



**Preliminary Factored Infiltration Rate<sup>1</sup>: 0.69 in/hr**

**Feasibility Screening Factor of Safety, F.S.<sup>2</sup>: 2.0**

**Temperature Correction Factor<sup>2,3</sup>: 0.86**

Factored Infiltration Rate <sup>2</sup>	Design Condition <sup>2</sup>
Below 0.05	No Infiltration
0.05 to 0.50	Partial Infiltration
Above 0.50	Full Infiltration

\*Porchet method used to convert percolation rate to infiltration rate.  
 1: Rate Factored by Factor of Safety and Temperature Correction Factor.  
 2: Reference: Riverside Design Handbook for Low Impact Development BMP (2011).  
 3: Factor based on as-tested water temperature of 71 F and rainfall temperature of 60 F.

<b>HCA Design and Construction</b> Riverside Community Hospital Riverside, California	<b>BOREHOLE PERCOLATION TEST I-6A</b> <b>INFILTRATION RATE</b>	<b>GROUP DELTA</b> PROJECT NUMBER: <b>SD809</b> FIGURE NUMBER: <b>D-6.1b</b>
---	---	--

# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/2/2024</u>	Borehole Radius (*r): <u>2 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/3/2024</u>	Casing Diameter: <u>2 in.</u>
Test Hole Number: <u>I-6B</u>	Tested By: <u>DMG</u>	Depth of Hole: <u>5.3 ft</u>
Drilling Method: <u>Hand Auger</u>	Temperature: <u>72 F</u>	Gravel Base Thickness: <u>4 in.</u>

## DATA SHEET

Reading Number	Time Interval (min.)	Cumulative Time (min.)	Initial Depth to Water (ft.)	Final Depth to Water (ft.)	Avg. Height of Water above Gravel Base (in.)		Measured Drop in Water Level (in.)	Corrected Drop in Water Level <sup>1</sup> (in.)	Corrected Percolation Rate <sup>1</sup> (in./hour)	Unfactored Infiltration Rate* (in./hour)
					H <sub>avg</sub>	H <sub>int</sub>				
	Δt	T	[from ground surface]				ΔH	ΔH <sub>c</sub>	ΔH <sub>c</sub> /Δt	I <sub>t</sub>
6	2.0	15	4.02	4.27	14.3	6.7*r	3.0	1.8	53.6	3.09
7	2.0	17	4.27	4.46	11.7	5*r	2.3	1.4	40.8	2.85
8	2.0	19	2.90	3.31	26.8	14.4*r	4.9	2.9	88.0	2.78
9	2.0	21	3.31	3.62	22.5	11.6*r	3.7	2.2	66.5	2.49
10	2.0	23	3.62	3.91	18.9	9.5*r	3.5	2.1	62.2	2.76
11	2.0	25	3.91	4.13	15.8	7.5*r	2.6	1.6	47.2	2.48
12	2.0	27	4.13	4.38	13.0	6*r	3.0	1.8	53.6	3.39
13	2.0	29	4.38	4.57	10.3	4.3*r	2.3	1.4	40.8	3.18
14	2.0	31	3.08	3.55	24.3	13.2*r	5.6	3.4	100.8	3.51
15	2.0	33	3.55	3.78	20.1	10*r	2.8	1.6	49.3	2.06
16	2.0	35	3.78	4.07	16.9	8.4*r	3.5	2.1	62.2	3.06
17	2.0	37	4.07	4.26	14.1	6.4*r	2.3	1.4	40.8	2.39
18	2.0	39	4.26	4.43	11.9	5.1*r	2.0	1.2	36.5	2.50
19	2.0	41	3.04	3.42	25.3	13.5*r	4.6	2.7	81.5	2.73
20	2.0	43	3.42	3.70	21.3	10.9*r	3.4	2.0	60.1	2.37
21	2.0	45	3.70	3.93	18.3	8.9*r	2.8	1.6	49.3	2.26
22	2.0	47	3.93	4.12	15.7	7.4*r	2.3	1.4	40.8	2.15
23	2.0	49	4.12	4.31	13.5	6.1*r	2.3	1.4	40.8	2.49
24	2.0	51	2.87	3.23	27.4	14.6*r	4.3	2.6	77.2	2.39
25	2.0	53	3.23	3.55	23.4	12.2*r	3.8	2.3	68.6	2.48
26	2.0	55	3.55	3.79	20.0	10*r	2.9	1.7	51.5	2.16
27	5.0	60	3.79	4.29	15.6	8.3*r	6.0	3.6	42.9	2.28
28	5.0	65	4.29	4.66	10.3	4.9*r	4.4	2.6	31.8	2.48
29	5.0	70	2.96	3.70	24.1	14*r	8.9	5.3	63.5	2.23
30	5.0	75	3.70	4.18	16.8	8.9*r	5.8	3.4	41.2	2.04
31	5.0	80	4.18	4.55	11.7	5.6*r	4.4	2.6	31.8	2.22
32	5.0	85	2.92	3.64	24.7	14.3*r	8.6	5.1	61.8	2.12
33	5.0	90	3.64	4.10	17.6	9.3*r	5.5	3.3	39.5	1.87
34	5.0	95	4.10	4.47	12.6	6.2*r	4.4	2.6	31.8	2.06
35	5.0	100	2.94	3.62	24.7	14.1*r	8.2	4.9	58.4	2.00
36	5.0	105	3.62	4.08	17.8	9.5*r	5.5	3.3	39.5	1.85
37	5.0	110	4.08	4.43	13.0	6.3*r	4.2	2.5	30.0	1.90
38	5.0	120	2.92	3.62	24.8	14.3*r	8.4	5.0	60.1	2.05
39	5.0	125	3.62	4.08	17.8	9.5*r	5.5	3.3	39.5	1.85
40	5.0	130	4.08	4.39	13.2	6.3*r	3.7	2.2	26.6	1.65

1: Porosity of gravel assumed to be 0.4 to correct drop in water.  
 \*Porchet method used to convert percolation rate to infiltration rate.

**Stabilized, Unfactored Infiltration Rate\*:** 1.95 inch/hour


<b>HCA Design and Construction</b> Riverside Community Hospital Riverside, California	<b>BOREHOLE PERCOLATION TEST I-6B</b> <b>INFILTRATION RATE</b>	PROJECT NUMBER <b>SD809</b>	FIGURE NUMBER <b>D-6.2a</b>
---	---	--------------------------------	--------------------------------



# BOREHOLE PERCOLATION TEST

Project Name: <u>Riverside Hospital</u>	Date Drilled: <u>4/2/2024</u>	Borehole Radius (*r): <u>2 in.</u>
Project Number: <u>SD809</u>	Date Tested: <u>4/3/2024</u>	Casing Diameter: <u>2 in.</u>
Test Hole Number: <u>I-6B</u>	Tested By: <u>DMG</u>	Depth of Hole: <u>5.3 ft</u>
Drilling Method: <u>Hand Auger</u>	Temperature <sup>3</sup> : <u>72 F</u>	Test Depth: <u>3 to 4 ft</u>

## UNFACTORED INFILTRATION RATES\* DURING TEST



**Preliminary Factored Infiltration Rate<sup>1</sup>: 0.83 in/hr**

**Feasibility Screening Factor of Safety, F.S.<sup>2</sup>: 2.0**

**Temperature Correction Factor<sup>2,3</sup>: 0.85**

Factored Infiltration Rate <sup>2</sup>	Design Condition <sup>2</sup>
Below 0.05	No Infiltration
0.05 to 0.50	Partial Infiltration
Above 0.50	Full Infiltration

\*Porchet method used to convert percolation rate to infiltration rate.  
 1: Rate Factored by Factor of Safety and Temperature Correction Factor.  
 2: Reference: Riverside Design Handbook for Low Impact Development BMP (2011).  
 3: Factor based on as-tested water temperature of 72 F and rainfall temperature of 60 F.

<b>HCA Design and Construction                  Riverside Community Hospital                  Riverside, California</b>	<b>BOREHOLE PERCOLATION TEST I-6B                  INFILTRATION RATE</b>	<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="font-size: small; text-align: center;">PROJECT NUMBER</td> <td style="font-size: small; text-align: center;">FIGURE NUMBER</td> </tr> <tr> <td style="text-align: center; font-weight: bold;">SD809</td> <td style="text-align: center; font-weight: bold;">D-6.2b</td> </tr> </table>	PROJECT NUMBER	FIGURE NUMBER	SD809	D-6.2b
PROJECT NUMBER	FIGURE NUMBER					
SD809	D-6.2b					

**APPENDIX E**  
**SITE-SPECIFIC SEISMIC HAZARD EVALUATION**

---

## APPENDIX B

### SITE-SPECIFIC SEISMIC HAZARD EVALUATION

#### E.1 INTRODUCTION

This section presents the results of the site-specific seismic hazard analysis per the 2022 California Building Code (CBC) and ASCE 7-16 (ASCE/SEI 7-16) for the project site. The subsurface soil conditions used in this study were obtained from our field exploration program including, hollow stem auger borings and seismic cone penetration tests (CPT), as well as prior downhole geophysical testing performed at the site to determine shear wave velocities.

Horizontal Acceleration Response Spectra (ARS) for 5-percent damping were developed for the Risk-Targeted Maximum Considered Earthquake ( $MCE_R$ ) as defined in Chapter 21.2 of ASCE 7-16. We performed both probabilistic and deterministic seismic hazard analyses. Site-specific probabilistic seismic hazard analyses were performed using the computer program OpenSHA (Field, 2003), with the seismic source model from the Uniform California Earthquake Rupture Forecast (UCERF3) Version 3 (Field et al, 2013). Development of the horizontal ARS was also performed using the ground motion models for the Next Generation Attenuation (NGA) – West 2 research project. The site coordinates used in our seismic hazard analyses are summarized below:

**Garage:** 33.9776 (latitude), -117.3834 (longitude)

**Tower:** 33.9765 (latitude), -117.3825 (longitude)

#### E.2 SEISMIC SETTING

The Riverside Community Hospital site is located in an area with high seismic activity. The approximate locations of nearby active faults are shown on the Regional Fault Map, Figure 5A. Table E-1 below lists the active faults that are closest to the site, and summarizes the Fault Type, Maximum Magnitude ( $M_w$ ) and Site-To-Source Rupture Distance ( $R_{rup}$ ). Note that the fault models we used generally follow UCERF3, which is the seismic source model developed by the Working Group on California Earthquake Probabilities (WGCEP) in 2013. The UCERF3 model was subsequently adopted by the 2014 U.S. National Seismic Hazard Mapping Program (NSHM) to develop probabilistic seismic hazard maps (Petersen et al., 2014).

The maximum magnitudes and scenarios adopted for our analyses are generally consistent with the published Building Seismic Safety Council 2014 Event Set, the adopted deterministic ruptures used for the 2014 USGS NSHM (BSSC, 2015). For multi-segment faults such as the Elsinore, San Jacinto, and San Andreas faults, where different earthquake scenarios are considered, the model producing the largest magnitude was reported in Table E-1 along with the combined segments.

**Table E-1. Significant Active Faults Near the Site**

Fault	Fault Type	Maximum Magnitude $M_w$	Site-to-Source Distance $R_{rup}$ (km)
San Jacinto (San Bernardino + San Jacinto Valley + Anza + Stepovers Combined + Coyote Creek + Borrego + Superstition Mountain)	Strike-Slip	7.8	13.0
Fontana (seismicity)	Strike-Slip <sup>(1)</sup>	6.8	14.4
Elsinore (Whittier + Glen Ivy + Temecula + Stepovers Combined + Julian + Coyote Mountains)	Strike-Slip	7.8	23.8
San Andreas (Parkfield + Cholame + Carrizo + Big Bend + North Mojave + South Mojave + North San Bernardino + South San Bernardino + San Gorgonio Pass - Garnet Hill + Coachella)	Strike-Slip	8.2	23.9
Chino (Alt 1 / Alt 2)	Strike-Slip	6.6 / 6.8 <sup>(2)</sup>	24.2 / 23.9
Cucamonga	Thrust	6.9	22.7
San Jose	Strike-Slip	6.7	32.1

**Notes:** (1) Faulting in Fontana was previously considered undetermined as it is based on seismicity. However, the latest edition of the recently released NSHM (2023) now considers this fault to be strike-slip.  
(2) Magnitudes presented are for the Chino fault alternatives (Alt 1 / Alt 2) respectively.

As shown in Table E-1, the closest known active seismic sources to the site include the San Jacinto fault zone and the San Andreas fault zone. These are some of the most active fault zones in California and are capable of producing some of the largest earthquakes. The closest active faults are discussed in more detail below.

The San Jacinto fault zone is located about 13.0 kilometers (km) northeast of the site. The San Jacinto fault zone is a right-lateral strike slip fault with a total length of about 210 km, extending from San Bernardino down south to Superstition Mountain. The northern end of the fault connects with the San Andreas fault zone. This fault is believed to be capable of producing earthquakes with a maximum moment magnitude ( $M_w$ ) of 7.8 when all of the fault segments rupture in combination from San Bernardino to Superstition Mountain. The San Jacinto fault has a typical recurrence interval for ground rupture of 100 to 300 years.

The Fontana fault has recently been identified based on frequent micro-seismicity in the area. It was not included in the 2008 edition of the NSHM but was added in 2014. Although initially the fault mechanism was not well understood, it is currently believed to be a strike-slip fault capable of producing earthquakes with magnitudes up to 6.8. According to UCERF3, this fault is “*likely a structure that actively transfers slip from the San Jacinto to the San Andreas.*” (Field, 2013).

The San Andreas fault zone is a right-lateral strike slip fault system that extends a total length of 315 miles (1,200 km) throughout California. This fault system forms the boundary between the Pacific Plate and the North American Plate. The Southern San Andreas section of the fault system extends from Parkfield down to its termination at the Salton Sea, with a length of 550 km. The Southern San Andreas section is estimated to be capable of producing earthquakes with a maximum magnitude ( $M_w$ ) of 8.2. In the area of Redlands and Yucaipa, the structure of the San Andreas fault becomes very complex due to interaction with other faults over the millennia, resulting in fractured segments and discontinuous branches. Recurrence intervals between ground-rupturing earthquakes vary on the San Andreas fault system depending on location. Near Los Angeles, this interval is estimated to be 175 to 200 years (USGS, 2017).

## E.2 HISTORIC SEISMICITY

There have been numerous moderate to large earthquakes located near the subject site over the last few centuries. A historical earthquake search was performed using the Advanced National Seismic System (ANSS) Comprehensive Earthquake Catalog (USGS, 2023). This search included earthquakes with magnitudes of 5.0 or higher and epicentral distances within 100 km of the center of the project site. The results are summarized below.

Time Period (1700 to April 2024)	324 years
Maximum Magnitude	$M_w \sim 7.5$
Number of Earthquakes with both $M_w > 5.0$ and $R_{RUP} < 100$ km	71

The earthquakes with epicenters closest to the site include the 1923  $M_w$  6.2 south San Bernardino earthquake which was located about 16.9 kilometers to the northeast of the site in the Santa Ana River, the 1858  $M_w$  6.0 earthquake north of San Bernardino, the 1990  $M_w$  5.5 Upland earthquake northwest of the site, and the 2008  $M_w$  5.4 Chino Hill earthquake west of the site. These earthquake epicenters are shown on the Regional Fault Map, Figure 5A. Other large earthquakes within 100 km of the site include the 1812  $M_w$  7.5 Wrightwood earthquake on the San Andreas fault northwest of the site, the 1992  $M_w$  7.3 Landers earthquake northeast of the site, and the 1899  $M_w$  6.7 San Jacinto earthquake southeast of the site.

## E.3 SITE CHARACTERIZATION

In developing site-specific ground motions, the characteristics of the soils underlying the site are an important input to evaluate the site response. In particular, the average shear wave velocity in the upper 30 meters ( $V_{s30}$ ) is a necessary parameter to perform seismic hazard analyses. Group Delta engaged a subcontractor to advance seismic CPT soundings at the project site to obtain shear wave velocity in the upper 30 meters or 100 feet. Three seismic CPTs were performed across the site, two within the proposed Garage site (CPT-1 and CPT-2), and one within the proposed Tower site (CPT-5). The CPT locations are shown on the Exploration Plans, Figures 3B and 3C.

In addition to the current measurements of shear wave velocity, prior geophysical studies at the site were reviewed and used to supplement the current measurements and data, particularly with respect to the shear wave velocity of the very dense Old Alluvium. All explorations at the site encountered refusal shallower than 100 feet in depth due to very dense granular soils in the Old Alluvium ( $N_{60} > 30$ ). The available data from the prior investigations was used to extrapolate shear wave velocity to depths of 100 feet to develop the  $V_{s30}$  values for use in our analyses (CHJ, 2008).

Based on the available data, including boring logs and soil samples, the shear wave velocity values were plotted based on their corresponding geology (i.e. existing fill, Young Alluvium, and Old Alluvium). Shear wave velocity measurements with depth are presented in Figure E-1 with respect to both exploration ID and interpreted geology. Within the Young Alluvium, the measured shear wave velocity values were generally between about 480 and 850 feet per second (ft/s), with a trend of low values near the surface, and increasing values with depth. The prior downhole geophysical study did interpret very low shear waves within the upper 5 feet. However, this measurement was taken prior to remedial grading. The existing fill soils have relatively high shear wave velocities ranging from about 760 to over 1,800 ft/s.

Below the surficial fill and Young Alluvium, the dense to very dense granular soils designated as Old Alluvium were observed to have much higher shear wave velocity values varying from about 1100 to over 2,500 ft/s (CHJ, 2008). Several measurements from our current seismic CPTs, as well as the prior downhole study all indicate that once embedded 10 to 15 feet in the Old Alluvium, the shear wave velocity values are generally 1,940 ft/s or greater. The deepest geophysical study at the site extended nearly 70 feet below grade and indicated shear wave velocities of 2,560 ft/s below a depth of 42 feet. Based on a review of all of the data,  $V_{s30}$  values for the proposed Garage and Tower sites were developed by extrapolating the Old Alluvium to a depth of 100 feet using a conservative lower bound of 1,940 ft/s for the Old Alluvium below refusal depth.

Based on the shear velocity profile measurements, the average shear wave velocity in the upper 100 feet ( $V_{s30}$ ) ranged from about 1,389 ft/s to 1,393 ft/s for CPT-1 and CPT-2, respectively. Therefore, a value of 1,390 ft/s or 424 meters per second [m/s] was adopted for the proposed Garage site. Based on CPT-5, a  $V_{s30}$  value of 1,598 ft/s or 487 m/s was adopted for the proposed Tower site. Both sites classify as Site Class C per ASCE 7-16.

#### **E.4 GROUND MOTION PREDICTION EQUATIONS**

Site-specific ground motions are influenced by type of faulting, magnitude of characteristic earthquakes, and local soil conditions. Many ground motion models, also referred to as Ground Motion Prediction Equations (GMPEs) have been developed to estimate the variation of spectral acceleration with earthquake magnitude and source-to-site distance, among other parameters. The Pacific Earthquake Engineering Research (PEER) coordinated a large multidisciplinary project entitled “NGA (Next Generation Attenuation)-West 2 Research Project” (Bozorgnia et al., 2014), referred to as NGA-West2.

In NGA-West2, five teams developed and presented horizontal ground motion models for shallow crustal earthquakes in active tectonic regions including Western North America. These teams were Abrahamson et al. (2014), Boore et al. (2014), Campbell and Bozorgnia (2014), Chiu and Youngs (2014), and Idriss (2014). All of the GMPEs were used in our analyses. However, as the Idriss (2014) model is only applicable to  $V_{S30}$  values over 450 m/s, it was used only for the Tower site. Where all five models were used, weights of 0.22 were assigned to all models but Idriss which was assigned a weight of 0.12. Where four were used, equal weight (0.25) was assigned.

The NGA-West2 relationships use measured values of shear wave velocity ( $V_{S,30}$ ) as input. As previously discussed, we adopted an average  $V_{S30}$  of 424 m/s at the proposed Garage and 487 m/s at the proposed Tower site to represent the underlying soil conditions. In addition, some of the ground motion models require input for  $Z_{1.0}$  (defined as the depth in meters to a shear wave velocity of 1 km/s) and  $Z_{2.5}$  (defined as the depth in km to a shear wave velocity of 2.5 km/s). These two parameters are used to capture the basin effect on site response. The SCEC Community Velocity Model (CVM) Version 4 was reviewed for selection of  $Z_{1.0}$  and  $Z_{2.5}$  values. A  $Z_{1.0}$  value of 150 m and a  $Z_{2.5}$  of 0.35 km were selected.

## E.5 PROBABILISTIC SEISMIC HAZARD ANALYSES

Site-specific Probabilistic Seismic Hazard Analyses (PSHA) were performed using the computer program OpenSHA (Fields, 2003), with the UCERF3 seismic source model and the updated NGA-West2 ground motion models. Uniform hazard horizontal ARS were developed up to a period of 10 seconds. The 5-percent damping hazard spectra are presented in Figures E-2a and E-2b.

Supplementary probabilistic seismic hazard analyses were performed using the USGS Unified Hazard Tool (<https://earthquake.usgs.gov/hazards/interactive/>) for comparison to the OpenSHA analyses. These analyses were performed using the dynamic version of the Conterminous U.S. 2014v4.2.0 at available spectral periods with the Site Class C/D option ( $V_{S30}$  of 360 m/s) and the Site Class C boundary ( $V_{S30}$  of 537 m/s). Results of these supplementary analyses show good agreement with the OpenSHA analyses.

The site-specific probabilistic  $MCE_R$  was developed in accordance with ASCE 7-16 Section 21.2.1, for the maximum horizontal component and adjusted for targeted risk of 1-percent probability of collapse in 50 years. The median (RotD50) ground motion was adjusted to the maximum rotated component of ground motion (RotD100) using maximum direction factors recommended by Shahi and Baker (2014). The second adjustment modifies the spectra from a 2-percent probability of exceedance in 50 years to a targeted risk of 1-percent probability of collapse in 50 years, which is performed using Method 1 of ASCE 7-16 (Section 21.2.1), using the risk coefficients  $C_{RS}$  and  $C_{R1}$ . The risk coefficients (per ASCE 7-16) were obtained using the Structural Engineers Association of California (SEAOC) and Office of Statewide Health Planning and Development (OSHPD) Seismic Design Maps website application (SEAOC/OSHPD, 2019). Risk coefficients  $C_{RS}$  of 0.941 and  $C_{R1}$  of 0.914 were used. The probabilistic  $MCE_R$  ARS for the site are shown in Figures E-2a and E-2b.

## E.6 DETERMINISTIC SEISMIC HAZARD ANALYSIS

Site-specific Deterministic Seismic Hazard Analyses (DSHA) were performed based on the characteristics of earthquake scenarios identified as predominant contributors to the regional seismic hazard. Pertinent characteristics of the earthquake scenarios include parameters such as distance from the site to the causative fault and the maximum magnitude of earthquake associated with the fault. The effects of local soil conditions ( $V_{s30}$ ) and the mechanism of faulting are accounted for in the ground motion models as well.

DSHAs were performed for four of the sources identified in Table E-1 above, the San Jacinto fault, the Fontana seismicity zone, the San Andreas fault, and the Elsinore fault. The NGA West2 GMMs were used to develop a 5-percent damped spectral ARS for each source. A plot of the DSHA results for the project site is shown in Figures E-3a and E-3b for each site. Note that the San Jacinto fault controls for spectral periods up to about 7.5 seconds, whereas the San Andreas fault begins to control seismic demand for the longer periods.

According to ASCE 7-16 Section 21.2.2, the deterministic  $MCE_R$ , which corresponds to the 84<sup>th</sup> percentile 5-percent damped spectral response accelerations in the direction of maximum horizontal response at any spectral period, must not be lower than deterministic lower limit. Therefore, the 84<sup>th</sup> percentile spectral values obtained from the GMPEs are used to develop the deterministic spectrum. The ground motions were adjusted to the maximum rotated component of ground motion using the ASCE 7-16 default maximum direction factors. Figures E-3a and E-3b shows the results of our DSHA along with ASCE 7-16 deterministic lower limit spectrum. The deterministic lower limit spectrum controls at the sites.

## E.7 DETERMINATION OF SITE-SPECIFIC RESPONSE SPECTRA

Development of the site-specific  $MCE_R$  ARS (as defined by Chapter 21.2 of ASCE 7-16) was performed using the seismic hazard analysis procedure described in the previous sections. In accordance with ASCE 7-16 Section 21.2.3, the site-specific  $MCE_R$  acceleration response spectra are taken as the lesser of the probabilistic and deterministic  $MCE_R$  spectra. The only exception is that the site-specific  $MCE_R$  ARS may be taken directly as the probabilistic  $MCE_R$  when the peak probabilistic spectrum is less than  $1.2 F_a$  (Section 21.2.3 of Supplement 1 to ASCE 7-16). In addition, per Section 21.3 of ASCE 7-16, the site-specific  $MCE_R$  cannot be not less than 150-percent of the 80-percent of design spectrum determined in accordance with Section 11.4.6 of ASCE 7-16. The resulting  $MCE_R$  spectra is presented in Figures E-4a and E-4b. For the project site, the deterministic  $MCE_R$  generally governs all spectral periods, with a few limited exceptions where the 150-percent minimum spectrum controls.

The site-specific Design Earthquake spectrum is equal to two-thirds of the site-specific  $MCE_R$  spectrum. The  $MCE_R$  and the Design Earthquake spectra along with the tabulated values for the project site are presented in Figures E-5a and E-5b.



## E.8 SITE-SPECIFIC DESIGN ACCELERATION PARAMETERS

The short period design spectral acceleration ( $S_{DS}$ ) and 1-second period design spectral acceleration ( $S_{D1}$ ) parameters were determined in accordance with ASCE 7-16 Section 21.4. The parameter  $S_{DS}$  is taken as 90-percent of the maximum spectral acceleration from the site-specific spectrum at periods between 0.2 and 5 seconds. The parameter  $S_{D1}$  is taken as the maximum of the product between period and spectral acceleration for periods from 1 to 2 seconds for sites with  $V_{S,30}$  greater than or equal to 365 m/s. The parameters  $S_{MS}$  and  $S_{M1}$  shall be taken as 1.5 times  $S_{DS}$  and  $S_{D1}$  respectively. The values obtained shall not be less than 80 percent of the values determined in accordance with ASCE 7-16, Section 11.4.3 for  $S_{MS}$  and  $S_{M1}$  and Section 11.4.4 for  $S_{DS}$  and  $S_{D1}$ . Table C-2 presents the site-specific design acceleration parameters.

Maximum Considered Earthquake-Geometric Mean,  $MCE_G$ , peak ground acceleration adjusted for site effects,  $PGA_M$ , was calculated in accordance with ASCE 7-16 Section 21.5. Per ASCE 7-16 Section 21.5,  $PGA_M$  shall be taken as the lesser of the probabilistic geometric mean peak ground acceleration and the deterministic geometric mean peak ground acceleration and shall not be less than the 80% of  $PGA_M$  obtained from Equation 11.8-1 of this code. The summary of  $MCE_R$  and Design Earthquake Site-Specific Seismic Hazard Analyses is provided in Tables E-3a and E-3b attached to this appendix.

**Table E-2: Site-Specific Seismic Design Acceleration Parameters**

Hazard Level	Parameter	Garage Site	Tower Site
$MCE_R$	$PGA_M$	0.600	0.611
	$S_{MS}$	1.620	1.620
	$S_{M1}$	0.896	0.790
Design Earthquake	$S_{DS}$	1.080	1.080
	$S_{D1}$	0.597	0.527

## ATTACHMENTS

Tables E-3a to E-3b Summary of  $MCE_R$  and Design Earthquake Site-Specific Seismic Hazard Analyses

## FIGURES

Figure E-1 Shear Wave Velocity Plots  
Figures E-2a to E-2b Probabilistic  $MCE_R$  Acceleration Response Spectra  
Figures E-3a to E-3b Deterministic Acceleration Response Spectra  
Figures E-4a to E-4b ASCE 7-16 Site-Specific  $MCE_R$  Acceleration Response Spectra  
Figures E-5a to E-5b ASCE 7-16 Site-Specific Design Earthquake and Acceleration Parameters

**Table E-3a: Summary of MCE<sub>R</sub> and Design Earthquake Site-Specific Seismic Hazard Analyses (Garage Site)**

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
Period (sec)	Probabilistic Sa <sub>RotD50</sub> (g)	Sa <sub>RotD100</sub> /Sa <sub>RotD50</sub>	Risk Coefficient, C <sub>R</sub>	Probabilistic MCE <sub>R</sub> (g)	Deterministic 84-%ile MCE, Sa <sub>RotD100</sub> (g)	Deterministic Lower Limit MCE (g)	Deterministic MCE <sub>R</sub> (g)	Site-Specific MCE <sub>R</sub> (g)	2/3 Site-Specific MCE <sub>R</sub> (g)	ASCE 7-16 Mapped Design ARS (g)	80% of Mapped Design ARS (g)	150% of 80%-Mapped Design ARS (g)	Final Site-Specific MCE <sub>R</sub> (g)	Final Design ARS (g)
0.01	0.837	1.19	0.941	0.938	0.695	0.754	0.754	0.754	0.503	0.557	0.446	0.669	0.754	0.503
0.02	0.846	1.19	0.941	0.947	0.702	0.762	0.762	0.762	0.508	0.634	0.507	0.761	0.762	0.508
0.03	0.906	1.19	0.941	1.015	0.743	0.806	0.806	0.806	0.538	0.711	0.569	0.854	0.854	0.569
0.05	1.124	1.19	0.941	1.258	0.878	0.953	0.953	0.953	0.635	0.866	0.693	1.039	1.039	0.693
0.075	1.455	1.19	0.941	1.629	1.084	1.176	1.176	1.176	0.784	1.059	0.847	1.270	1.270	0.847
0.1	1.690	1.19	0.941	1.893	1.243	1.349	1.349	1.349	0.899	1.200	0.960	1.440	1.440	0.960
0.15	1.913	1.2	0.941	2.160	1.475	1.601	1.601	1.601	1.067	1.200	0.960	1.440	1.601	1.067
0.2	1.996	1.21	0.941	2.273	1.605	1.742	1.742	1.742	1.161	1.200	0.960	1.440	1.742	1.161
0.25	1.983	1.22	0.939	2.273	1.659	1.800	1.800	1.800	1.200	1.200	0.960	1.440	1.800	1.200
0.3	1.898	1.22	0.938	2.172	1.653	1.794	1.794	1.794	1.196	1.200	0.960	1.440	1.794	1.196
0.4	1.648	1.23	0.934	1.893	1.545	1.677	1.677	1.677	1.118	1.200	0.960	1.440	1.677	1.118
0.5	1.464	1.23	0.931	1.676	1.409	1.529	1.529	1.529	1.020	1.120	0.896	1.344	1.529	1.020
0.75	1.078	1.24	0.922	1.233	1.074	1.166	1.166	1.166	0.777	0.747	0.597	0.896	1.166	0.777
1	0.809	1.24	0.914	0.916	0.826	0.896	0.896	0.896	0.597	0.560	0.448	0.672	0.896	0.597
1.5	0.521	1.24	0.914	0.591	0.551	0.598	0.598	0.591	0.394	0.373	0.299	0.448	0.591	0.394
2	0.377	1.24	0.914	0.427	0.397	0.430	0.430	0.427	0.285	0.280	0.224	0.336	0.427	0.285
3	0.249	1.25	0.914	0.284	0.263	0.286	0.286	0.284	0.190	0.187	0.149	0.224	0.284	0.190
4	0.187	1.26	0.914	0.215	0.193	0.210	0.210	0.210	0.140	0.140	0.112	0.168	0.210	0.140
5	0.151	1.26	0.914	0.173	0.149	0.161	0.161	0.161	0.108	0.112	0.090	0.134	0.161	0.108
7.5	0.093	1.28	0.914	0.109	0.085	0.092	0.092	0.092	0.061	0.075	0.060	0.090	0.092	0.061
10	0.062	1.29	0.914	0.073	0.054	0.058	0.058	0.058	0.039	0.045	0.036	0.054	0.058	0.039

Column Descriptions



- 1 Spectral period
- 2 2% in 50 year, RotD50 Probabilistic ARS
- 3 Factors to adjust to Maximum Direction (Shahi & Baker, 2014)
- 4 Risk Coefficients Per Method 1 of ASCE 7-16 Section 21.2.1, obtained from SEAOC/OSHPD Seismic Design Maps tool (SEAOC/OSPHD, 2022).
- 5 Probabilistic MCE<sub>R</sub> ARS, adjusted for maximum direction of horizontal response and targeted risk of 1% probability of collapse in 50 years (columns 2 x 3 x 4) per ASCE 7-16 Section 21.2.1
- 6 Upper envelop of 84-percentile, Deterministic ARS adjusted for maximum direction for all sources. Not required where Peak Sa from Probabilistic MCE<sub>R</sub> is less than 1.2Fa per ASCE 7-16 Supplement 1 Section 21.2.2
- 7 Deterministic Lower Limit (Peak Sa must be at least 1.5\*Fa) in accordance with Supplement 1 of ASCE 7-16. Not required where Peak Sa from Probabilistic MCE<sub>R</sub> is less than 1.2Fa per ASCE 7-16 Supplement 1 Section 21.2.2
- 8 Deterministic MCE<sub>R</sub> (greater of columns 6 and 7) per ASCE 7-16 Section 21.2.2. Not required where Peak Sa from Probabilistic MCE<sub>R</sub> is less than 1.2Fa per ASCE 7-16 Supplement 1 Section 21.2.2
- 9 Site-Specific MCE<sub>R</sub> (lesser of Deterministic MCE<sub>R</sub> and Probabilistic MCE<sub>R</sub>, or lesser of columns 5 and 8) in accordance with Section 21.2.3 of ASCE 7-16
- 10 2/3 of Column 9 per Equation 21.3-1 of ASCE 7-16 Section 21.3
- 11 Mapped Design Earthquake ARS in accordance with ASCE 7-16 Section 11.4.7 as modified by Section 21.3
- 12 80% of Mapped Design Earthquake ARS (lower limit check) per Section 21.4
- 13 150% of the 80% of Mapped Design Earthquake ARS (MCE lower limit check per ASCE 7-16 Supplement 1 Section 21.3)
- 14 Final Site-Specific MCE<sub>R</sub> ARS per Section 21.2.3 (greater of columns 9 and 13)
- 15 Final Design Earthquake ARS per Section 21.3 (greater of columns 10 and 12)

**Table E-3b: Summary of MCE<sub>R</sub> and Design Earthquake Site-Specific Seismic Hazard Analyses (Tower Site)**

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
Period (sec)	Probabilistic Sa <sub>RotD50</sub> (g)	Sa <sub>RotD100</sub> /Sa <sub>RotD50</sub>	Risk Coefficient, C <sub>R</sub>	Probabilistic MCE <sub>R</sub> (g)	Deterministic 84-%ile MCE, Sa <sub>RotD100</sub> (g)	Deterministic Lower Limit MCE (g)	Deterministic MCE <sub>R</sub> (g)	Site-Specific MCE <sub>R</sub> (g)	2/3 Site-Specific MCE <sub>R</sub> (g)	ASCE 7-16 Mapped Design ARS (g)	80% of Mapped Design ARS (g)	150% of 80%-Mapped Design ARS (g)	Final Site-Specific MCE <sub>R</sub> (g)	Final Design ARS (g)
0.01	0.822	1.19	0.941	0.921	0.727	0.784	0.784	0.784	0.523	0.557	0.446	0.669	0.784	0.523
0.02	0.833	1.19	0.941	0.932	0.738	0.796	0.796	0.796	0.530	0.634	0.507	0.761	0.796	0.530
0.03	0.899	1.19	0.941	1.007	0.792	0.854	0.854	0.854	0.569	0.711	0.569	0.854	0.854	0.569
0.05	1.134	1.19	0.941	1.270	0.933	1.006	1.006	1.006	0.670	0.866	0.693	1.039	1.039	0.693
0.075	1.478	1.19	0.941	1.655	1.169	1.261	1.261	1.261	0.840	1.059	0.847	1.270	1.270	0.847
0.1	1.711	1.19	0.941	1.916	1.344	1.449	1.449	1.449	0.966	1.200	0.960	1.440	1.449	0.966
0.15	1.922	1.2	0.941	2.170	1.579	1.702	1.702	1.702	1.135	1.200	0.960	1.440	1.702	1.135
0.2	1.979	1.21	0.941	2.254	1.665	1.796	1.796	1.796	1.197	1.200	0.960	1.440	1.796	1.197
0.25	1.936	1.22	0.939	2.218	1.669	1.800	1.800	1.800	1.200	1.200	0.960	1.440	1.800	1.200
0.3	1.790	1.22	0.938	2.047	1.585	1.709	1.709	1.709	1.139	1.200	0.960	1.440	1.709	1.139
0.4	1.547	1.23	0.934	1.777	1.442	1.555	1.555	1.555	1.036	1.200	0.960	1.440	1.555	1.036
0.5	1.358	1.23	0.931	1.555	1.292	1.393	1.393	1.393	0.929	1.120	0.896	1.344	1.393	0.929
0.75	0.994	1.24	0.922	1.136	0.951	1.025	1.025	1.025	0.684	0.747	0.597	0.896	1.025	0.684
1	0.745	1.24	0.914	0.844	0.732	0.789	0.789	0.789	0.526	0.560	0.448	0.672	0.789	0.526
1.5	0.484	1.24	0.914	0.549	0.489	0.527	0.527	0.527	0.351	0.373	0.299	0.448	0.527	0.351
2	0.352	1.24	0.914	0.399	0.358	0.386	0.386	0.386	0.257	0.280	0.224	0.336	0.386	0.257
3	0.234	1.25	0.914	0.268	0.250	0.270	0.270	0.268	0.179	0.187	0.149	0.224	0.268	0.179
4	0.178	1.26	0.914	0.205	0.189	0.203	0.203	0.203	0.136	0.140	0.112	0.168	0.203	0.136
5	0.144	1.26	0.914	0.166	0.150	0.162	0.162	0.162	0.108	0.112	0.090	0.134	0.162	0.108
7.5	0.091	1.28	0.914	0.106	0.091	0.098	0.098	0.098	0.065	0.075	0.060	0.090	0.098	0.065
10	0.061	1.29	0.914	0.072	0.058	0.063	0.063	0.063	0.042	0.045	0.036	0.054	0.063	0.042

Column Descriptions

- 1 Spectral period
- 2 2% in 50 year, RotD50 Probabilistic ARS
- 3 Factors to adjust to Maximum Direction (Shahi & Baker, 2014)
- 4 Risk Coefficients Per Method 1 of ASCE 7-16 Section 21.2.1, obtained from SEAOC/OSHPD Seismic Design Maps tool (SEAOC/OSPHD, 2022).
- 5 Probabilistic MCE<sub>R</sub> ARS, adjusted for maximum direction of horizontal response and targeted risk of 1% probability of collapse in 50 years (columns 2 x 3 x 4) per ASCE 7-16 Section 21.2.1
- 6 Upper envelop of 84-percentile, Deterministic ARS adjusted for maximum direction for all sources. Not required where Peak Sa from Probabilistic MCE<sub>R</sub> is less than 1.2Fa per ASCE 7-16 Supplement 1 Section 21.2.2
- 7 Deterministic Lower Limit (Peak Sa must be at least 1.5\*Fa) in accordance with Supplement 1 of ASCE 7-16. Not required where Peak Sa from Probabilistic MCE<sub>R</sub> is less than 1.2Fa per ASCE 7-16 Supplement 1 Section 21.2.2
- 8 Deterministic MCE<sub>R</sub> (greater of columns 6 and 7) per ASCE 7-16 Section 21.2.2. Not required where Peak Sa from Probabilistic MCE<sub>R</sub> is less than 1.2Fa per ASCE 7-16 Supplement 1 Section 21.2.2
- 9 Site-Specific MCE<sub>R</sub> (lesser of Deterministic MCE<sub>R</sub> and Probabilistic MCE<sub>R</sub>, or lesser of columns 5 and 8) in accordance with Section 21.2.3 of ASCE 7-16
- 10 2/3 of Column 9 per Equation 21.3-1 of ASCE 7-16 Section 21.3
- 11 Mapped Design Earthquake ARS in accordance with ASCE 7-16 Section 11.4.7 as modified by Section 21.3
- 12 80% of Mapped Design Earthquake ARS (lower limit check) per Section 21.4
- 13 150% of the 80% of Mapped Design Earthquake ARS (MCE lower limit check per ASCE 7-16 Supplement 1 Section 21.3)
- 14 Final Site-Specific MCE<sub>R</sub> ARS per Section 21.2.3 (greater of columns 9 and 13)
- 15 Final Design Earthquake ARS per Section 21.3 (greater of columns 10 and 12)



PROJECT NAME

**Riverside Community Hospital  
445 Magnolia Avenue, Riverside**

FIGURE NAME

**Shear Wave Velocity Plots**



**GROUP DELTA**


PROJECT NUMBER

SD809


FIGURE NUMBER


E-1

Probabilistic Seismic Hazard Analyses  
5% Damping




Probabilistic  $MCE_R$  (ASCE 7-16, Section 21.2.1)  
5% Damping





PROJECT NAME	FIGURE NAME	 <b>GROUP DELTA</b>	
<b>Riverside Community Hospital - Garage</b> <b>4445 Magnolia Avenue</b>	<b>Probabilistic Acceleration</b> <b>Response Spectra</b>		

Probabilistic Seismic Hazard Analyses  
5% Damping




Probabilistic  $MCE_R$  (ASCE 7-16, Section 21.2.1)  
5% Damping





PROJECT NAME	FIGURE NAME	 <b>GROUP DELTA</b>	
<b>Riverside Community Hospital - Tower 4445 Magnolia Avenue</b>	<b>Probabilistic Acceleration Response Spectra</b>		

Deterministic MCE (84<sup>th</sup>-percentile,  $S_{a_{RotD50}}$ )  
5% Damping




Deterministic MCE<sub>R</sub> (ASCE 7-16, 21.2.2)  
5% Damping





PROJECT NAME	FIGURE NAME		
<b>Riverside Community Hospital - Garage</b> <b>4445 Magnolia Avenue</b>	<b>Deterministic Acceleration</b> <b>Response Spectra</b>		

Deterministic MCE (84<sup>th</sup>-percentile,  $Sa_{RotD50}$ )  
5% Damping




Deterministic MCE<sub>R</sub> (ASCE 7-16, 21.2.2)  
5% Damping




<p>PROJECT NAME</p> <p><b>Riverside Community Hospital - Tower 4445 Magnolia Avenue</b></p>	<p>FIGURE NAME</p> <p><b>Deterministic Acceleration Response Spectra</b></p>	 <p><b>GROUP DELTA</b></p> <p>PROJECT NUMBER</p> <p><b>SD809</b></p>	<p>FIGURE NUMBER</p> <p><b>E-3b</b></p>
---	--	---	---





Site-Specific Risk-Targeted Horizontal  $MCE_R$  (ASCE 7-16, Section 21.2)  
5% Damping



PROJECT NAME	FIGURE NAME	 <b>GROUP DELTA</b>	
<b>Riverside Community Hospital - Garage</b> <b>4445 Magnolia Avenue</b>	<b>ASCE 7-16 Site-Specific MCE<sub>R</sub></b> <b>Acceleration Response Spectra</b>	PROJECT NUMBER SD809	FIGURE NUMBER E-4a


Site-Specific Risk-Targeted Horizontal  $MCE_R$  (ASCE 7-16, Section 21.2)  
5% Damping



PROJECT NAME	FIGURE NAME	 <b>GROUP DELTA</b>	
<b>Riverside Community Hospital - Tower 4445 Magnolia Avenue</b>	<b>ASCE 7-16 Site-Specific MCE<sub>R</sub> Acceleration Response Spectra</b>	PROJECT NUMBER SD756	FIGURE NUMBER E-4b

ASCE 7-16 $MCE_R$ and Design Earthquake		
Period	Design	$MCE_R$
(sec)	$S_a$ (g)	$S_a$ (g)
0.01	0.503	0.754
0.02	0.508	0.762
0.03	0.569	0.854
0.05	0.693	1.039
0.075	0.847	1.270
0.1	0.960	1.440
0.15	1.067	1.601
0.2	1.161	1.742
0.25	1.200	1.800
0.3	1.196	1.794
0.4	1.118	1.677
0.5	1.020	1.529
0.75	0.777	1.166
1	0.597	0.896
1.5	0.394	0.591
2	0.285	0.427
3	0.190	0.284
4	0.140	0.210
5	0.108	0.161
7.5	0.061	0.092
10	0.039	0.058

Site-Specific Design Earthquake (ASCE 7-16, Section 21.3)  
5% Damping



**Site-Specific Design Acceleration Parameters (ASCE 7-16 Section 21.4)**

$S_{DS}$  = 90% of the peak  $S_a$  from  $T=0.2$  to 5 s (not less than 80% of mapped  $S_{DS}$ )

$S_{D1}$  = Peak  $T \cdot S_a$  between periods of 1 second and 2 seconds (not less than 80% of mapped  $S_{D1}$ )


$S_{DS} = 1.080 \quad S_{D1} = 0.597$

PROJECT NAME		FIGURE NAME	
Riverside Community Hospital - Garage 4445 Magnolia Avenue		ASCE 7-16 Site-Specific Design Earthquake and Site-Specific Design Acceleration Parameters	
		SD809	E-5a



ASCE 7-16 $MCE_R$ and Design Earthquake		
Period	Design	$MCE_R$
(sec)	$S_a$ (g)	$S_a$ (g)
0.01	0.523	0.784
0.02	0.530	0.796
0.03	0.569	0.854
0.05	0.693	1.039
0.075	0.847	1.270
0.1	0.966	1.449
0.15	1.135	1.702
0.2	1.197	1.796
0.25	1.200	1.800
0.3	1.139	1.709
0.4	1.036	1.555
0.5	0.929	1.393
0.75	0.684	1.025
1	0.526	0.789
1.5	0.351	0.527
2	0.257	0.386
3	0.179	0.268
4	0.136	0.203
5	0.108	0.162
7.5	0.065	0.098
10	0.042	0.063

Site-Specific Design Earthquake (ASCE 7-16, Section 21.3)  
5% Damping



**Site-Specific Design Acceleration Parameters (ASCE 7-16 Section 21.4)**

$S_{DS}$  = 90% of the peak  $S_a$  from  $T=0.2$  to  $5$  s (not less than 80% of mapped  $S_{DS}$ )


$S_{D1}$  = Peak  $T \cdot S_a$  between periods of 1 second and 2 seconds (not less than 80% of mapped  $S_{D1}$ )

$S_{DS} = 1.080 \quad S_{D1} = 0.527$

PROJECT NAME		FIGURE NAME			
<b>Riverside Community Hospital - Tower 4445 Magnolia Avenue</b>		<b>ASCE 7-16 Site-Specific Design Earthquake and Site-Specific Design Acceleration Parameters</b>			PROJECT NUMBER
				SD809	FIGURE NUMBER
					E-5b

# Appendix F - Existing and Proposed Drainage Maps

Plotted By: Conzalez, Ana Sheet: Set:Kha Layout:Layout1 January 21, 2025 07:46:19pm K:\GRA\_LDEV\0909270009 - Riverside Community Hospital Phase 2\CADD\Exhibits\Engineering\Drainage\Garage Existing Conditions Drainage.dwg  
 This document, including all text and graphics, is the property of Kimley-Horn and Associates, Inc. and is loaned to the client for their specific purpose and shall not be used for any other purpose without the written consent of Kimley-Horn and Associates, Inc. All rights are reserved. No part of this document may be reproduced or transmitted in any form or by any means, electronic or mechanical, including photocopying, recording, or by any information storage and retrieval system, without the prior written permission of Kimley-Horn and Associates, Inc.




- LEGEND**
- 575 --- EXISTING CONTOUR
  - PROPERTY LINE
  - - - - - DMA BOUNDARY
  - DA XX  
XX AC
  - EXISTING STORM DRAIN
  - LANDSCAPED AREAS
  - FLOW PATH

- DRAINAGE KEYNOTES**
- ① EXISTING INLET
  - ② EXISTING INFILTRATION SYSTEM
  - ③ EXISTING VALLEY GUTTER

**PRE-DEVELOPMENT FLOWS (UNMITIGATED)**


DRAINAGE AREA	AREA (AC)	RATIONAL METHOD (CFS)		UPSTREAM NODE # AND ELEVATION (FT)	DOWNSTREAM NODE # AND ELEVATION (FT)	FLOW PATH LENGTH (FT)
		10-YEAR	100-YEAR			
A	2.27	3.09	5.09	Node 10 809.2	Node 11 792.7	581
B	1.01	1.38	3	Node 20 793.4	Node 21 793	165
<b>Total</b>	<b>3.28</b>	<b>4.47</b>	<b>8.09</b>	-	-	-

Drainage Area	Area (ac)	2-Year Unit Hydrograph (cfs)			
		1-hr	3-hr	6-hr	24-hr
A	2.27	2.3	1.19	0.97	0.37
		5-Year Unit Hydrograph (cfs)			
		3.03	1.62	1.35	0.5
		10-Year Unit Hydrograph (cfs)			
		3.69	2.07	1.79	0.6
100-Year Unit Hydrograph (cfs)					
		5.69	-	-	1.08



<p><b>RIVERSIDE COMMUNITY HOSPITAL NEW BROCKTON PARKING GARAGE</b></p> <p>PRE-DEVELOPMENT CONDITION</p>	<p><b>Kimley-Horn</b></p> <p>1100 TOWN AND COUNTRY RD, SUITE 700, ORANGE, CA 92668        PHONE: 714-938-1030 FAX: 714-938-4488        WWW.KIMLEY-HORN.COM</p>															
<p>PROJECT: PARKING GARAGE PRE-DEVELOPMENT CONDITION</p> <p>DATE: 1/20/25</p> <p>SCALE: AS SHOWN</p> <p>DRAWN BY: AG</p> <p>CHECKED BY: LAC</p>	<p>REVISIONS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>No.</th> <th>DATE</th> <th>BY</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>	No.	DATE	BY												
No.	DATE	BY														
<p>RIVERSIDE COMMUNITY HOSPITAL NEW BROCKTON PARKING GARAGE</p> <p>RIVERSIDE, CA</p>	<p>REVISIONS</p>															

File: 01 - 2024-001701 - RIVERSIDE COMMUNITY HOSPITAL NEW BROCKTON PARKING GARAGE - POST-DEVELOPMENT CONDITION (PHASE 1) - CIVIL - 11/10/24.dwg  
 PR-2024-001701 (GPA, SPA, RZ, DR) Exhibit 13 - EIR Addendum and appendices



**LEGEND**

- 575 PROPOSED CONTOUR
- 575 EXISTING CONTOUR
- PROPERTY LINE
- DMA BOUNDARY
- DRAINAGE AREA NAME  
AREA (IN ACRES)
- NODE ID AND ELEVATION
- PROPOSED STORM DRAIN
- EXISTING STORM DRAIN
- LANDSCAPED AREAS
- GRAVEL AREAS
- FLOW PATH

**DRAINAGE KEYNOTES**

- PROPOSED INLET
- PROPOSED INFILTRATION SYSTEM
- PROPOSED VALLEY GUTTER
- PROPOSED PRETREATMENT UNIT

PR-BMP-1  
PROPOSED CONTECH  
INFILTRATION CMP SYSTEM  
TOTAL VOLUME=10,941 CF  
WQ VOLUME PROVIDED=2,745 CF

**EX. MEDICAL  
OFFICE BUILDING  
4510  
BROCKTON**

**EX. MEDICAL  
OFFICE  
BUILDING  
4500  
BROCKTON**

**EX. PARKING GARAGE  
4550 BROCKTON**

**COMMUNITY  
PLAYERS BLDG.  
4026 14TH  
STREET**

**EX. BLDG. G**

**EX. BLDG. C  
4445  
MAGNOLIA**

**POST-DEVELOPMENT FLOWS (UNMITIGATED)**


DRAINAGE AREA	AREA (AC)	RATIONAL METHOD (CFS)		UPSTREAM NODE # AND ELEVATION (FT)	DOWNSTREAM NODE # AND ELEVATION (FT)	FLOW PATH LENGTH (FT)
		10-YEAR	100-YEAR			
A1.1	0.08	0.15	0.25	Node 10 804	Node 11 798	95
A1.2	0.21	0.34	0.54	Node 20 803.1	Node 21 794.3	400
A1.3	0.99	1.89	3.05	Node 30 N/A	Node 31 N/A	N/A
A1.4	0.01	0.02	0.03	Node 40 795	Node 41 794.7	17
A1.5	0.54	0.92	1.48	Node 80 794.7	Node 81 791.7	230
A1.6	0.05	0.1	0.15	Node 60 796.6	Node 61 794.9	109
A1.7	0.04	0.08	0.12	Node 70 797.9	Node 71 796.6	105
A2	1.34	2.05	3.31	Node 90 809	Node 91 792.5	574
B	0.02	0.04	0.06	Node 100 N/A	Node 101 N/A	N/A
<b>Total</b>	<b>3.28</b>	<b>5.59</b>	<b>8.99</b>			

Drainage Area	Area (ac)	2-Year Unit Hydrograph (cfs)			
		1-hr	3-hr	6-hr	24-hr
A1	1.92	2.06	0.94	0.75	0.28
A2	1.34	1.43	0.69	0.54	0.2
<b>Total</b>	<b>3.26</b>	<b>3.49</b>	<b>1.63</b>	<b>1.29</b>	<b>0.48</b>

Drainage Area	Area (ac)	5-Year Unit Hydrograph (cfs)			
		1-hr	3-hr	6-hr	24-hr
A1	1.92	2.74	1.31	1.06	0.38
A2	1.34	1.89	0.96	0.79	0.27
<b>Total</b>	<b>3.26</b>	<b>4.63</b>	<b>2.27</b>	<b>1.85</b>	<b>0.65</b>

Drainage Area	Area (ac)	10-Year Unit Hydrograph (cfs)			
		1-hr	3-hr	6-hr	24-hr
A1	1.92	3.37	1.72	1.45	0.46
A2	1.34	2.31	1.24	1.06	0.32
<b>Total</b>	<b>3.26</b>	<b>5.68</b>	<b>2.96</b>	<b>2.51</b>	<b>0.78</b>


Drainage Area	Area (ac)	100-Year Unit Hydrograph (cfs)	
		1-hr	24-hr
A1	1.92	5.25	0.87
A2	1.34	3.57	0.64
<b>Total</b>	<b>3.26</b>	<b>8.82</b>	<b>1.51</b>



<p><b>Kimley»Horn</b></p> <p style="font-size: 8px;">© 2024 KIMLEY-HORN AND ASSOCIATES, INC. 1100 TOWN AND COUNTRY RD SUITE 700, ORANGE, CA 92668 PHONE: 714-938-0330 FAX: 714-938-9488 WWW.KIMLEY-HORN.COM</p>	<p>REVISED BY</p> <p>NO.</p> <p>DATE</p>
<p>LICENSED PROFESSIONAL</p> <p>PROJECT: 090670009</p> <p>DATE: 11/10/24/25</p> <p>SCALE: AS SHOWN</p> <p>DESIGNED BY: AC</p> <p>DRAWN BY: AC</p> <p>CHECKED BY: LAC</p>	<p>RIVERSIDE COMMUNITY HOSPITAL NEW BROCKTON PARKING GARAGE POST-DEVELOPMENT CONDITION (PHASE 1)</p>
<p><b>RIVERSIDE COMMUNITY HOSPITAL NEW BROCKTON PARKING GARAGE</b></p> <p>POST-DEVELOPMENT CONDITION (PHASE 1)</p>	<p>SHEET NUMBER</p>

PR-2024-001701 (GPA, SPA, RZ, DR) Exhibit 13 - EIR Addendum and appendices

FILED BY: *[Signature]* DATE: 1/10/25  
 RIVERSIDE COMMUNITY HOSPITAL NEW BROCKTON PARKING GARAGE  
 1100 TOWN AND COUNTRY RD, SUITE 700, ORANGE, CA 92668  
 PHONE: 714-939-1030 FAX: 714-939-9488  
 WWW.KIMLEY-HORN.COM



**LEGEND**

- 575 PROPOSED CONTOUR
- 575 EXISTING CONTOUR
- PROPERTY LINE
- DMA BOUNDARY
- DA XX  
XX AC DRAINAGE AREA NAME  
AREA (IN ACRES)
- NODE 10  
50.00 FS NODE ID AND ELEVATION
- SD PROPOSED STORM DRAIN
- SD EXISTING STORM DRAIN
- LANDSCAPED AREAS
- FLOW PATH

- DRAINAGE KEYNOTES**
- 1 PROPOSED INLET
  - 2 PROPOSED INFILTRATION SYSTEM
  - 3 PROPOSED VALLEY GUTTER
  - 4 PROPOSED PRETREATMENT UNIT

PR-BMP-1  
 PROPOSED CONTECH  
 INFILTRATION CMP SYSTEM  
 TOTAL VOLUME=10,941 CF  
 WQ VOLUME PROVIDED=2,745 CF

**EX. MEDICAL  
 OFFICE BUILDING  
 4510  
 BROCKTON**

**EX. PARKING GARAGE  
 4550 BROCKTON**

**EX. MEDICAL  
 OFFICE  
 BUILDING  
 4500  
 BROCKTON**

**COMMUNITY  
 PLAYERS BLDG.  
 4026 14TH  
 STREET**

**EX. BLDG. G**

**EX. BLDG. C  
 4445  
 MAGNOLIA**

**POST-DEVELOPMENT FLOWS (UNMITIGATED)**

DRAINAGE AREA	AREA (AC)	RATIONAL METHOD (CFS)		UPSTREAM NODE # AND ELEVATION (FT)	DOWNSTREAM NODE # AND ELEVATION (FT)	FLOW PATH LENGTH (FT)
		10-YEAR	100-YEAR			
A1.1	0.08	0.15	0.25	Node 10 804	Node 11 798	95
A1.2	0.21	0.34	0.54	Node 20 803.1	Node 21 794.3	400
A1.3	0.99	1.89	3.05	Node 30 N/A	Node 31 N/A	N/A
A1.4	0.01	0.02	0.03	Node 40 795	Node 41 794.7	17
A1.5	0.54	0.92	1.48	Node 80 794.7	Node 81 791.7	230
A1.6	0.05	0.1	0.15	Node 60 796.6	Node 61 794.9	109
A1.7	0.04	0.08	0.12	Node 70 797.9	Node 71 796.6	105
A2	1.34	2.05	3.31	Node 90 809	Node 91 792.5	574
B	0.02	0.04	0.06	Node 100 N/A	Node 101 N/A	N/A
<b>Total</b>	<b>3.28</b>	<b>5.59</b>	<b>8.99</b>			

**2-Year Unit Hydrograph (cfs)**

Drainage Area (ac)	1-hr	3-hr	6-hr	24-hr
A1	1.92	2.06	0.94	0.75
A2	1.34	1.43	0.69	0.54
<b>Total</b>	<b>3.26</b>	<b>3.49</b>	<b>1.63</b>	<b>1.29</b>

**5-Year Unit Hydrograph (cfs)**


Drainage Area (ac)	1-hr	3-hr	6-hr	24-hr
A1	1.92	2.74	1.31	1.08
A2	1.34	1.89	0.96	0.79
<b>Total</b>	<b>3.26</b>	<b>4.63</b>	<b>2.27</b>	<b>1.85</b>

**10-Year Unit Hydrograph (cfs)**

Drainage Area (ac)	1-hr	3-hr	6-hr	24-hr
A1	1.92	3.37	1.72	1.45
A2	1.34	2.31	1.24	1.06
<b>Total</b>	<b>3.26</b>	<b>5.68</b>	<b>2.96</b>	<b>2.51</b>

**100-Year Unit Hydrograph (cfs)**

Drainage Area (ac)	1-hr	24-hr
A1	1.92	5.25
A2	1.34	3.57
<b>Total</b>	<b>3.26</b>	<b>8.82</b>



**Kimley Horn**  
 LICENSED PROFESSIONAL  
 KHA PROJECT: 090670009  
 DATE: 1/10/25  
 SCALE: AS SHOWN  
 DESIGNED BY: AC  
 DRAWN BY: LAC  
 CHECKED BY: LAC  
 RIVERSIDE COMMUNITY HOSPITAL NEW BROCKTON PARKING GARAGE  
 PARKING GARAGE POST-DEVELOPMENT CONDITION (PHASE 1 ULTIMATE BUILDOUT)  
 SHEET NUMBER: CA